



## ADDENDUM #2

### SILVERTON SHORES PARK AND WINGFIELD TRAIL

**BID #17/18-006 / PWP #WA-2017-244**

**BIDS DUE NO LATER THAN: 1:45 PM ON AUGUST 9, 2017 - REVISED**

**PUBLIC BID OPENING: 2:00 PM ON AUGUST 9, 2017 - REVISED**

This addendum is to notify all potential proposers of clarifications made to the Bid documents as stated below.

#### **Bid Due Date Changed from Original Date of August 3, 2017 to Revised Date of August 9, 2017**

Bids must be in the hands of the Contracts and Risk Manager at 431 Prater Way, Sparks, Nevada, NO LATER THAN **1:45 PM ON August 9, 2017**. Bids postmarked prior to, but not received until after this deadline will not be accepted. Bids will be opened and publicly read at **2:00 PM ON August 9, 2017**.

**BID SCHEDULE: (2<sup>nd</sup> REVISED BID ITEM SCHEDULE ATTACHED)** – Please use the 2<sup>nd</sup> revised Bid Item Schedule in place of Pages 4-9 of the original Bid Document, previously replaced by Pages 3-8 of Addendum #1. Changes include:

Item 16.0 – NEW – Park Site Drainage Improvements. This is to include all excavation, storm drain piping, backfill, F.E.S., Yard Drains with 3’ radius of 12” minus rip rap for complete site storm drain system.

Item A4.0 – DELETED – This item is part of Alternate B Dog Park option and is included in Bid Item B10.0

#### **CLARIFICATIONS:**

1. The Park Site drainage was missing from the Base Bid. Bid Item 16.0 is for the Park Site drainage which will include all excavation, backfill, piping, yard drains with 3’ radius of 12” minus rip rap constructed around them, FES and all appurtenance necessary for the park site drainage as shown on the plans and to the back of curb tie in point to the playground drainage.
2. Base Bid Item 10.0 will be for the playground drainage system only to the back of curb where it ties into the site drainage of the park.
3. Alternate A4.0 is deleted from the bid schedule. This item is part of Alternate B Dog Park option and is covered in Item B10.0

Please note and adjust your bid according to the revisions, additions, deletions, clarifications or modifications as presented on this Addendum #2, which are made a part of this bid. NOTE: To avoid disqualification, this Addendum 2 (and any other addenda) must be signed by an authorized

representative of the bidding firm in the space provided and must be submitted with your firm's sealed proposal. Failure to return this addendum, duly signed, may be cause for rejection of the bid. ALL ADDENDA SHOULD BE SIGNED AND PLACED IN SEQUENTIAL ORDER AND ATTACHED TO THE FRONT OF THE BID PACKAGE, COMPLETE WITH ALL REQUIRED DOCUMENTS.

\_\_\_\_\_  
CONTRACTOR BUSINESS NAME

X \_\_\_\_\_  
Authorized Signature

\_\_\_\_\_  
Printed Name of Person Signing

\_\_\_\_\_  
Dan Marran, C.P.M., CPPO  
Contracts and Risk Manager

August 1, 2017

**CITY OF SPARKS**  
**BID ITEM SCHEDULE – 2<sup>ND</sup> REVISION (ADDENDUM #2)**

**BID #** 17/18-006  
**PWP #WA-2017-244**

**BID TITLE:** Silverton Shores Park and Wingfield Trail

**PRICES** must be valid for 90 calendar days after the bid opening.

**COMPLETION** of this project is expected **PURSUANT TO CONTRACT DOCUMENTS.**

**BIDDER** acknowledges receipt of \_\_\_\_\_ Addenda.

\_\_\_\_\_  
Bidder Name

\_\_\_\_\_  
(signature)

**Silverton Shores Park Area Base Bid**

Item No.	Quantity	Unit	Description	Unit Price	Total Price
1.0	1	LS	Mob/Demob/SWPP per lump sum	\$ _____ /LS	\$ _____
2.0	4,100	CY	Clearing, grubbing, earthwork, and grading complete and in place per cubic yard.	\$ _____ /CY	\$ _____
3.0	1	LS	Electrical improvements complete and in place per lump sum.	\$ _____ /LS	\$ _____
4.0	1	LS	Permanent irrigation from POC throughout park complete and in place per lump sum.	\$ _____ /LS	\$ _____
5.0	1	LS	Temporary irrigation system including main valves, laterals and impact heads complete and in place per lump sum.	\$ _____ /LS	\$ _____
6.0	3,250	SF	Construct 6" PCC on 4" Type II aggregate base traffic rated sidewalk complete and in place per square foot.	\$ _____ /SF	\$ _____
7.0	5,250	SF	Construct 4" PCC on 4" Type II aggregate base sidewalk complete and in place per square foot.	\$ _____ /SF	\$ _____
8.0	145	LF	Construct 8" x 12" PCC Play Ground curbing complete and in place per lineal foot.	\$ _____ /LF	\$ _____

Item No.	Quantity	Unit	Description	Unit Price	Total Price
9.0	1	LS	Install owner supplied 2-5 & 5-12 playground complete and in place per lump sum.	\$ _____ /LS	\$ _____
10.0	1	LS	Construction Playground area drainage to site storm drain system complete in place per lump sum.	\$ _____ /LS	\$ _____
11.0	3,750	SF	Construct 16" depth playground bark fall safety material with fabric complete and in place per square foot.	\$ _____ /SF	\$ _____
12.0	36	EA	Supply and install 8' Evergreen trees complete and in place per each.	\$ _____ /EA	\$ _____
13.0	2.05	AC	Construct irrigated revegetation seed area complete and in place per acre	\$ _____ /AC	\$ _____
14.0	3	EA	Supply and install 6' benches complete and in place per each.	\$ _____ /EA	\$ _____
15.0	2	EA	Supply and install double benches with shade structures complete and in place per each.	\$ _____ /EA	\$ _____
16.0	1	LS	Construct Park Site drainage to include all excavation, backfill, piping materials, etc. for complete drainage system as shown on the plans complete and in place per lump sum.	\$ _____ /LS	\$ _____
17.0	1	EA	Supply and install 4' square table with ADA access complete and in place per each.	\$ _____ /EA	\$ _____
18.0	1	EA	Supply and install basketball standard complete and in place per each	\$ _____ /EA	\$ _____
19.0	1	LS	Construct basketball striping complete and in place per lump sum	\$ _____ /EA	\$ _____
20.0	280	LF	Construct split rail fence complete and in place per lineal foot.	\$ _____ /LF	\$ _____
21.0	1	FA	Force Account	\$ 15,000.00	\$ 15,000.00
22.0	2	EA	Construct PCC ADA Playground Ramp with Type II aggregate base, complete and in place per each	\$ _____ /EA	\$ _____

<b>Total Silverton Shores Base Bid Price</b>	
\$ _____	\$ _____
(written total bid price)	

### Wingfield Trail Base Bid

Item No.	Quantity	Unit	Description	Unit Price	Total Price
W1.0	1	LS	Mob/Demob/SWPP per lump sum	\$ _____ /LS	\$ _____
W2.0	4,450	SF	Remove existing AC pathway to accommodate new PCC trail complete and in place per square foot	\$ _____ /SF	\$ _____
W3.0	1	EA	Demolition and removal of existing evergreen tree complete per each	\$ _____ /EA	\$ _____
W4.0	10,000	SF	Construct 6" PCC on 4" Type II aggregate base traffic rated trail complete and in place per square foot.	\$ _____ /SF	\$ _____
W5.0	2	EA	Construct traffic barrier gates complete and place per each	\$ _____ /EA	\$ _____
W6.0	1	EA	Construct collapsible bollard complete and place per each	\$ _____ /EA	\$ _____
W7.0	0.62	AC	Construct non-irrigated dryland revegetation seed area complete and in place per acre	\$ _____ /AC	\$ _____
W8.0	0.14	AC	Construct irrigated dryland revegetation seed area complete and in place per acre	\$ _____ /AC	\$ _____
W9.0	395	LF	Construct 2 rail split rail fence complete and in place per lineal foot	\$ _____ /LF	\$ _____
W10.0	4	EA	Supply and install 3'x 3' min granite boulders at trail entrance complete and in place per each	\$ _____ /EA	\$ _____
W11.0	1	FA	Force Account	\$ <u>15,000.00</u>	\$ <u>15,000.00</u>

<b>Total Wingfield Trail Base Bid</b>  \$ _____ <p style="text-align: center;">(written total price)</p>	\$ _____
---	----------

**BASE BID RECAP**

<b>Total Silverton Shores Base Bid Price</b>	\$ _____
<b>Total Wingfield Trail Base Bid</b>	\$ _____
<b>TOTAL BASE BID</b>	\$ _____

**PLEASE NOTE:** Bid ranking, evaluation and award recommendation will be made using the “Total Base Bid.” Use of any or all of the bid alternates (below) in the awarded contract will only be determined after the apparent low bidder is identified using the “Total Base Bid.”

Once the apparent low bidder is determined using the “Total Base Bid,” “Alternate Bid” totals may be considered for inclusion in the resulting contract, depending on available funding. Alternate Bids may be considered/awarded in no particular order.

### Silverton Shores Park Area Alternate A

Item No.	Quantity	Unit	Description	Unit Price	Total Price
A1.0	3,750	SF	Construct PCC concrete pad under playground area complete and in place per square foot.	\$ _____ /SF	\$ _____
A2.0	3,750	SF	Supply and install rubber tile safety fall material complete and in place per square foot.	\$ _____ /SF	\$ _____
A3.0	1	LS	Construct drainage improvements for rubber tile playground complete and in place per lump sum	\$ _____ /LS	\$ _____
A4.0	0	SF	<b>DELETED</b>	\$ <u>N/A</u> /SF	\$ <u>N/A</u>
A5.0	1	LS	Deduct for not installing playground bark fall safety material with fabric, PCC ADA ramps, and Playground footings.	\$ _____ /LS	(\$ _____)
A6.0	1	LS	Deduct for not installing bark playground drainage system per lump sum	\$ _____ /LS	(\$ _____)

<b>Total Silverton Shores Alternate A Price</b>  \$ _____ <p style="text-align: center;">(written total price)</p>	\$ _____
---	----------

### Silverton Shores Park Area Alternate B

Item No.	Quantity	Unit	Description	Unit Price	Total Price
B1.0	675	LF	Construct 6' wide compacted DG pathway with soil stabilizer complete and in place per lineal foot.	\$ _____ /LF	\$ _____
B2.0	6,715	SF	Construct compacted DG dog park area complete and in place per square foot.	\$ _____ /SF	\$ _____
B3.0	335	LF	Construct 4' high dog park CLF complete and in place per lineal foot	\$ _____ /LF	\$ _____
B4.0	2	EA	Construct 4' high dog park CLF gate complete and in place per each	\$ _____ /EA	\$ _____
B5.0	1	LS	Construct dog park irrigation system complete and in place per lump sum	\$ _____ /LS	\$ _____
B6.0	1	EA	Supply and install pet waste station complete and in place per each	\$ _____ /EA	\$ _____
B7.0	5	EA	Supply and install 6' benches complete and in place per each.	\$ _____ /EA	\$ _____
B8.0	0.25	AC	Deduct for reduction of irrigated reveg area per acre	\$ _____ /AC	\$ _____
B9.0	0.25	AC	Deduct for reduction of temporary irrigation of irrigated reveg area per acre	\$ _____ /AC	\$ _____
B10.0	120	SF	Construct 4" PCC on 4" Type II aggregate base sidewalk at dog park. Complete and in place per square foot.	\$ _____ /SF	\$ _____
B11.0	36	SF	Construct PCC Valley Gutter and Type II aggregate base per detail complete and in place per square foot	\$ _____ /SF	\$ _____

<b>Total Silverton Shores Alternate B Price</b>  \$ _____ <p style="text-align: center;">(written total price)</p>	\$ _____
---	----------