

**CITY OF SPARKS
INFORMAL QUOTE SCHEDULE**

Rock Blvd. and McCARRAN Bridge Concrete Pathway Replacement

Contractor/Supplier: Anchor Concrete Name of Authorized Representative: Daniel Price Title: Pres.
 SIGNATURE of Authorized Representative: [Signature] Date: 6/7/2012
 [An authorized representative of the bidding firm shall sign this document in the space(s) provided. An unsigned bid may be disqualified]
 ADDRESS: 1750 Marietta Way CITY: Sparks STATE: NV ZIP: 89431
 Telephone Number(s): Office Number: (775) 359-4969 Facsimile Number: (775) 359-4407
 Federal Tax Identification Number # 88-0112162
 CONTRACTORS LICENSE #: 1192, 16421, 172954178 Expiration Date: 2/28/14 License limitations \$ 6,000,000.
 Contractor qualified by State Contractors Board Yes No City Of Sparks Business License No. (If Applicable): 052072

ONE (1) COMPLETE QUOTE PROPOSAL and ANY ADDENDUM(s) MUST BE DELIVERED TO CITY OF SPARKS, ATTN: Andy Echelta, CAPITAL PROJECTS COORDINATOR, 431 PRATER WAY, SPARKS, NV 89431, FAX# (775) 353-1635, BY 1:00 P.M. ON JUNE 7, 2012.

F.O.B.: DESTINATION SITE SPARKS, NEVADA – PREPAID

Rock Blvd Bridge Crossing Quote:

QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1.0 Lump Sum	Demolition and Removal of Existing Improvements complete at \$ <u>four thousand six hundred and 00/100</u> /per lump sum	\$ <u>4,600.00</u> /LS	\$ <u>4,600.00</u>
2.0 200 LF	6 inch thick 12 foot wide Portland Cement Concrete pathway on 4" Aggregate Base including thickened edge 8" wide 8" thick (one side only), complete and in place at \$ <u>Fifty seven and 00/100</u> /per lineal foot	\$ <u>57.00</u> /LF	\$ <u>11,400.00</u>
3.0 125 LF	6 inch thick 10 foot wide Portland Cement Concrete pathway on 4" Aggregate Base complete and in place at \$ <u>Fifty and 00/100</u> /per lineal foot	\$ <u>50.00</u> /LF	\$ <u>6,250.00</u>
4.0 200 LF	6 inch wide x 18" tall PCC Curb including 2, #4 rebar continuous complete and in place at \$ <u>Twenty two and 00/100</u> /per lineal foot	\$ <u>22.00</u> /LF	\$ <u>4,400.00</u>
TOTAL ROCK CROSSING QUOTE			\$ <u>26,650.00</u>

McCarran Bridge Crossing Quote:				
	QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL PRICE
5.0	Lump Sum	Demolition and Removal of Existing Improvements complete at \$ <u>Three thousand three hundred + 00/100</u> /per lump sum	\$ <u>3,300.00</u> /LS	\$ <u>3,300.00</u>
6.0	220 LF	6 inch thick 12 foot wide Portland Cement Concrete pathway on 4" Aggregate Base including thickened edge 8" wide 8" thick (one side only), complete and in place at \$ <u>Fifty seven + 00/100</u> /per lineal foot	\$ <u>57.00</u> /LF	\$ <u>12,540.00</u>
7.0	140 LF	6 inch wide x 18" tall PCC Curb including 2, #4 rebar continuous complete and in place at \$ <u>Twenty five + 00/100</u> /per lineal foot	\$ <u>25.00</u> /LF	\$ <u>3,500.00</u>
8.0	lump	Force Account	\$ <u>5,000.00</u>	\$ <u>5,000.00</u>
TOTAL McCARRAN CROSSING QUOTE			\$ <u>24,340.00</u>	
Total Rock Crossing and McCarran crossing Quote			\$ <u>50,990.00</u>	

Rock and McCarran Concrete Pathway Replacement

INFORMAL QUOTE CLARIFICATIONS

Item 1.0, 5.0

This item includes the removal and disposal of all asphalt, concrete, etc. as per field meeting. The bid price shall also include all labor, materials, equipment, traffic control, disposal, and fees as necessary to complete the work. Payment for this item is per lump sum.

Item 2.0, 6.0

This item consists of constructing all new 6" thick 12' wide 4000 PSI City mix PCC pathway on new aggregate base. The bid price shall also include all labor, materials, equipment, traffic control, and concrete blankets as necessary to complete the work. The bid quantity shall be the plan quantity unless work is added to or deleted from the contract by the City of Sparks. Payment for this item is per square foot.

Item 3.0

This item consists of constructing all new 6" thick 10' wide 4000 PSI City mix PCC pathway on new aggregate base. The bid price shall also include all labor, materials, equipment, traffic control, and concrete blankets as necessary to complete the work. The bid quantity shall be the plan quantity unless work is added to or deleted from the contract by the City of Sparks. Payment for this item is per square foot.

Item 4.0, 7.0

This item consists of constructing new 6" wide 18" high curb using 4000 PSI City mix PCC on new aggregate base as shown on the plans and details. The bid price shall also include all labor, materials, equipment, and traffic control, and concrete blankets as necessary to complete the work. The bid quantity shall be the plan quantity unless work is added to or deleted from the contract by the City of Sparks. Payment for this item is per lineal foot.