

2904 Duluth Street W. Sacramento, CA 95691 916-372-9692 **Quote #: 22688** 

Date: 12/30/201 CustID: 31654

Thank you for the opportunity to quote your business, please call if you have any questions.

City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432 City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432

Attn: Ron Korman

Qty>=	Description	Unit Price	Ext Price
2	Remove Tenco Dump Body	\$1,150.00	\$2,300.00
	THIS PRICING IS CONSISTENT WITH COUNTY OF EL DORADO CONTRACT P0201418715 FOR REMOVAL OF OLD DUMP BODY AND INSTALLATION OF NEW DUMP BODY		
	14' BODY INSTALLED ON INTERNATIONAL CHASSIS WITH 132" C/T		
	REMOVE BODY BUT LEAVE ALL HYDRAULICS AND REAR HITCH PLATE		

Terms of Sale:	Tom's House of Hydraulics
Net30	Authorized by:senochian
	Date: 8/21/2014



2904 Duluth Street W. Sacramento, CA 95691 916-372-9692 Quote #: 22688

Page 2 of 4

Date: 12/30/201

CustID: 31654

Thank you for the opportunity to quote your business, please call if you have any questions.

City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432 City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432

Attn: Ron Korman

Qty>=	Description	Unit Price	Ext Price
2	Dump Body: 15' Galion 550FT	\$24,498.00	\$48,996.00
	HYDRAULIC POWER FOR BODY TO BE CONTROLLED BY CERTIFIED POWER CENTRAL HYDRAULIC SYSTEM		
	(REQUIRES 132" C/T)		
	- Capacity: 13.6 to 16.2 cubic yards - Floor: 3/16" AR450 with 2" Floor to Side Radius - Sides: 3/16" Hi-Tensile Steel, 42" High w/ Cheater Board Holders - Headboard: 3/16" Hi-Tensile Steel, 50" High - Tailgate: 3/16" Hi-Tensile Steel Double Acting Tailgate, 50" High, (9) Panel, Air Release - 12" X 3/16" Spreader Apron with Hinged Bottom and Rubber Sides Bolted to Body - 1/2 Cab Protector, 8ga Hi-Tensile Steel - Shovel Holder mounted to drivers side headboard - Fold Down ladder on passenger side front corner - Front, Trunnion Mounted Cylinder - Lighting to FMVSS108 - Mud Flaps - Body Prop - Body Painted White - Installed		

Terms of Sale:	Tom's House of Hydraulics
Net30	Authorized by:senochian
	Date: 9/21/2014



2904 Duluth Street W. Sacramento, CA 95691 916-372-9692 Quote #: 22688

Page 3 of 4

Date: 12/30/201

CustID: 31654

Thank you for the opportunity to quote your business, please call if you have any questions.

City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432 City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432

Attn: Ron Korman

Qty>=	Description	Unit Price	Ext Price
2	Hydraulic System: Parts, Sand Spreader/Pre-Wet System	\$16,189.00	\$32,378.00
	CERTIFIED POWER COMPONENTS:  1) LOAD SENSE VALVE BANK  2) IN-CAB CONSOLE  3) ALL HARNESSES, CABLES, BRACKETS, AND HOSES TO COMPLETE INSTALLATION		
	COMPONENTS TO BE REUSED ARE THE HYDRAULIC RESERVOIR AND VALVE ENCLOSURE AND PUMP		

Terms of Sale:	Tom's House of Hydraulics
Net30	Authorized by: senochian
	Date:_8/21/2014



2904 Duluth Street W. Sacramento, CA 95691 916-372-9692 Quote #: 22688

Page 4 of 4

Date: 12/30/201

CustID: 31654

Thank you for the opportunity to quote your business, please call if you have any questions.

City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432 City of Sparks Fleet Maintenance 215 South 21st St Sparks, NV 89432

Attn: Ron Korman

Qty>=	Description	Unit Price	Ext Price
2	Hydraulic System: Labor, Sand Spreader/Pre-Wet System	\$5,030.00	\$10,060.00
	THIS ESTIMATE COVERS THE COST TO INSTALL THE HYDRAULIC CIRCUITS FOR AN ALL-IN-ONE SNOW CONTROL UNIT (REF: HENDERSON FIRST RESPONSE) WHICH INCLUDES (4) HYDRAULIC PRESSURE CIRCUITS (AUGER, SPINNER, ANTI-ICE, PRE-WET) AND (1) COMMON RETURN. THESE HOSES WILL RUN FROM THE CERTIFIED POWER VALVE BOX TO THE REAR OF THE TRUCK AND BE TERMINATED WITH QUICK DISCONNECT FITTINGS.  A SINGLE POINT ELECTRICAL HARNESS WILL BE INSTALLED WITH A DISCONNECT AT THE END OF THE TRUCK. THIS PRICE DOES NOT INCLUDE THE HARNESS.  LABOR ONLY TO UPPGRADE THE CERTIFIED POWER CENTRAL HYDRAULIC SYSTEM.		
		TOTAL	\$93,734.00

Terms of Sale:	Tom's House of Hydraulics
Net30	Authorized by:senochian
	Date: 8/21/2014