

# GEOTECHNICAL INVESTIGATION REPORT PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT SPARKS, NEVADA

November 11, 2009

Copyright 2009 Kleinfelder All Rights Reserved

ONLY THE CLIENT OR ITS DESIGNATED REPRESENTATIVES MAY USE THIS DOCUMENT AND ONLY FOR THE SPECIFIC PROJECT FOR WHICH THIS REPORT WAS PREPARED.



4835 Longley Lane Reno, NV 89502

pi 775.689.7800 f | 775.689.7810

kleinfelder.com

November 11, 2009 File: 102314.104

HDR Engineering, Inc. 9805 Double R Boulevard, Suite 101 Reno, NV 89521

Attention:

Mr. Noel Laughlin, P.E.

**SUBJECT: Geotechnical Investigation Report** 

**Proposed North Truckee Drain Realignment** 

Sparks, Nevada

Dear Mr. Laughlin:

The attached report presents the results of our geotechnical investigation to support design of the proposed North Truckee Drain (NTD) Realignment in Sparks, Nevada. Our work consisted of review of available information, obtaining applicable permits, performing subsurface exploration, laboratory testing, engineering analyses, and preparation of this report.

We understand the proposed project includes approximately 2.5 miles of box culverts extending from the Interstate 80 at Sparks Boulevard to the Truckee River. The proposed alignment crosses several significant structures including Interstate 80, Union Pacific Railroad (UPRR) tracks, the existing NTD open channel, the East Greg Street embankment, and outfalls into the Truckee River.

Based on the results of our study, we observed no severe soil or groundwater constraints that would preclude project development. The encountered subsurface soils generally consisted of clayey to silty sand fill with varying amounts of gravel, underlain by native lean to fat clay overlying very dense granular glacial outwash deposits. Groundwater levels generally corresponded to approximately the top of the outwash deposits. We anticipate that major design items will include shoring and temporary slopes associated with excavations, subgrade stabilization to establish a working construction platform

in the native clays, and construction dewatering below the groundwater table. These and other conclusions and recommendations, along with restrictions and limitations regarding them, are discussed in the attached report.

4835 Longley Lane Reno, NV 89502

p| 775.689.7800 f| 775.689.7810 kleinfelder.com

We appreciate this opportunity to be of service to you, and look forward to future endeavors. If you have any questions regarding this report or need additional information or services, please feel free to call one of the undersigned in our Reno office.

Sincerely,

KLEINFELDER WEST, INC.

Don Adams, P.E.

Staff Professional

Jønathan Pease, P.E., Ph.D.

Senior Geotechnical Engineer

Enclosures: Report (5 Bound)

Scott Smith, P.E., Ph.D. Senior Principal Engineer



#### **TABLE OF CONTENTS**

CH	APIER		PAGE
1.	INTR	RODUCTION AND SCOPE	
	1.1	Introduction	
	1.2	Project Description	
	1.3	Purpose and Scope of Work	
	1.4	Authorization	
	1.5	References	
2.	MET	HODS OF STUDY	5
	2.1	Literature Review	5
	2.2	Field Exploration	5
	2.3	Monitoring Wells	7
	2.4	Laboratory Testing	8
3.	DISC	CUSSION	9
-	3.1	Regional Geology and Faulting	9
		3.1.1 Seismic Design Parameters	
	3.2	Site Geology	
	3.3	Site Conditions	
	3.4	Subsurface Conditions	
		3.4.1 <u>Fill</u>	
		3.4.2 <u>Native Material</u>	
		3.4.3 <u>Groundwater</u>	17
	3.5	<u>Liquefaction</u>	19
4.	CON	CLUSIONS	21
5.	REC	OMMENDATIONS	23
	5.1	General Recommendations	23
	5.2	Site Clearing and Preparation	23
	5.3	Earthwork	24
	5.4	Subgrade Preparation and Subgrade Stabilization.	25
		5.4.1 Subgrade Stabilization	
		5.4.2 Pre-Cast RCB Construction	
		5.4.3 Cast-in-Place RCB Construction	
		5.4.4 Improvements Founded Near Final Grade	∍27
	5.5	Trenching and Excavation	
	5.6	Construction Dewatering	
	5.7	Temporary Excavation Slopes	
	5.8	Shoring	
	5.9	Recommended Permanent Slope Angles	
	5.10	Foundations	
		5.10.1 Hydrostatic Uplift Pressures	34
	5.11	Retaining Structures and Lateral Earth Pressures .	
	5.12	Special Areas	

i

K	LEINFELDER
1	Bright People. Right Solutions.

		5.12.1 Adjacent to the Existing NTD Channel		
		5.12.2 East Greg Street Embankment		
		5.12.3 Truckee River Levee and NTD Outfall		
	5.13			
	5.14	Steel and Concrete Reactivity	40	
6.	ADDI	ITIONAL SERVICES	41	
	6.1	Project Bid Documents		
	6.2	Construction Observation/Testing and Plan Review	41	
7.	LIMIT	TATIONS	43	
8.	REFE	ERENCES	44	
TABL	.ES			
			<u>Page</u>	
1	Boring	g Coordinates	6	
2	Sumn	mary of Encountered Fill Thickness and Elevations	13	
3	Sumn	mary of Tahoe Outwash Depths and Elevations	14	
4	Sumn	mary of Groundwater Depths and Elevations	16	
5	Sumn	mary of Encountered Subsurface Conditions and Elevation of RCB	20	
6		num Allowable Temporary Excavation Slopes	29	
7		ninary Lateral Earth Pressures with Hydrostatic Pressures	32	
8		ninary Lateral Earth Pressures without Hydrostatic Pressures	33	
9	Recor	mmended Minimum Factors of Safety	33	
PLAT	EG			
PLAI	LJ			
1	Site P	Plan		
2 to 1	6 Logs	s of Boring		
17	-	o Soil Classification and Terms		
18	•	o Boring Logs		
	-	poratory Testing Results		
31		Term Groundwater Elevations in Project Vicinity		
APPE	NDICE	ES		
Α	Previo	ous Boring Logs		
В		Lab Results		
С	Sections of Groundwater Report, Broadbent & Associates, Inc., 2008			



# GEOTECHNICAL INVESTIGATION REPORT PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT SPARKS, NEVADA

#### 1. INTRODUCTION AND SCOPE

#### 1.1 <u>Introduction</u>

This report presents the results of Kleinfelder's geotechnical investigation for the proposed realignment of the North Truckee Drain (NTD), a storm water drainage facility in the southeastern portion of the City of Sparks, Nevada. This project is being designed by HDR Inc. for the City of Sparks. Information regarding the proposed construction presented in this report was obtained from preliminary plans by HDR (2009) and in various conversations and meetings with HDR and the City of Sparks.

#### 1.2 <u>Project Description</u>

The project location is shown on the Site Plan, Plate 1. The proposed project consists of realignment and replacement of the existing NTD to carry the design flood flow of a 117-year storm with an increased level of flood protection for the adjacent and upstream areas of eastern Sparks. The proposed NTD modifications are from Interstate 80 east of Sparks Boulevard to the Truckee River, near the Vista Narrows. The existing NTD is an open channel which flows east and then south to join the Truckee River. The existing NTD channel joins the Truckee River about 700 feet southwest of the intersection of Kleppe Lane and East Greg Street, approximately 3,700 feet upstream of the Vista Narrows.

The project concept has advanced since the start of our geotechnical investigations. Initially, replacement of the existing NTD culvert under Interstate 80 and the UPRR tracks with new larger culverts was considered necessary to provide the required additional capacity. Construction of the culvert using open excavations or jacking was under consideration. The current plan instead splits the flow beneath Interstate 80 and UPRR tracks between the NTD and the People's Drain, a former agricultural drain ditch,



which crosses under the Interstate 80 and the UPRR tracks about 850 feet west of the existing NTD culvert. Dividing the flow through both drains provides adequate capacity under the Interstate 80 and the UPRR tracks without the need to replace the main culverts.

South of Interstate 80 and the UPRR tracks, the proposed NTD (and additional outflow from the People's Drain) will be routed through new reinforced concrete box culverts (RCBs) which will run east, parallel to the UPRR tracks, to East Greg Street. Two alignments, a base and an alternate alignment, were initially considered downstream from East Greg Street.

The base alignment turns south for approximately 400 feet before crossing under the East Greg Street embankment. The base alignment would be constructed under the northern leg of Larkin Circle, and outfall into the Truckee River would be about 200 feet from the edge of the street immediately downstream of the Vista Narrows. This outfall is approximately 3,700 feet downriver from the existing NTD confluence with the Truckee River.

An alternate alignment was considered that bent slightly southward to avoid a fiber-optic line junction east of the East Greg Street embankment, but otherwise proceeded east within the UPRR right-of-way about 200 feet south of the UPRR mainline. This alternate alignment was proposed to intercept the Truckee River about 1,300 feet downriver of the Vista Narrows, or about 5,000 feet downstream of the existing confluence. Although several soil borings were drilled along this alternate alignment, the proposed alternate has been eliminated and geotechnical recommendations for this alternate route are not discussed in this report.

Based on the draft plans, upstream of where the People's Drain and the NTD rejoin, the proposed box culverts are to be double 8-foot by 8-foot RCBs (16 feet nominal width). Downstream from this junction, the NTD will be built as double 14-foot-wide by 10-foot-high RCBs (28-feet nominal width). Both sizes can be built with cast-in-place concrete or two side-by-side pre-cast segments. For most of the alignment, backfill over the RCBs will be between 2 and 8 feet thick. The entire alignment will be designed for HS-20 truck loadings. At East Greg Street, the RCB will be built below an embankment approximately 20 feet high. A specific discussion on this and other special conditions are addressed in Section 5.12.



#### 1.3 Purpose and Scope of Work

The purpose of this investigation was to evaluate the feasibility of the proposed infrastructure improvements with respect to the observed subsurface conditions, and to provide our geotechnical recommendations and opinions to support the project design and construction. Our scope of services consisted of background review, site reconnaissance, field exploration, laboratory testing, engineering analyses, and preparation of this report. As outlined in our proposal dated April 23, 2008 and amended in a Modification to Scope letter dated June 24, 2009, the items listed below were to be addressed in the final report:

- Provide a brief description of geologic setting, general seismicity, and local geologic hazards based on a review of available literature;
- Discuss general soil and groundwater conditions including the subsurface profile encountered at the project site, with emphasis on how the conditions are expected to affect the proposed construction;
- Recommendations for temporary excavations, including preliminary slopes and possible retaining systems;
- Lateral earth pressures and drainage recommendations for RCBs and retaining structures;
- Construction recommendations for the proposed drainage facilities, including identification of anticipated construction difficulties; and,
- Potential for site soils to corrode steel, or to adversely react with concrete.

This study did not include site-specific evaluations of seismicity, fault trenching, other potential geologic or environmental hazards, or pavement design recommendations.



#### 1.4 <u>Authorization</u>

Authorization to proceed with our work on this project was provided by HDR on February 23, 2008 in the form of a signed Geotechnical Subconsultant Agreement.

#### 1.5 References

Partial improvements plans for the North Truckee Drain Realignment by HDR dated June 10, 2009 were provided to Kleinfelder in the course of this study and serve as the basis of our understanding of the project type and scope.

## KLEINFELDER Bright People. Right Solutions.

#### 2. METHODS OF STUDY

2.1 <u>Literature Review</u>

A literature review was previously performed and summarized in a *Phase 1 Data Report* (Kleinfelder, 2007) which consisted of compiling and reviewing available geotechnical-related information that was provided to Kleinfelder. The results of the literature review were compiled on a plate which showed historic boring locations previously performed by others, boring surface elevations, depth of measured groundwater, estimated depth to Tahoe Outwash deposits, and soil layers identified above the Tahoe Outwash deposit.

#### 2.2 Field Exploration

As part of the *Phase 1 Data Report* (Kleinfelder 2007) two preliminary soil borings were drilled for the project in January 2007. One of these borings was located on Larkin Circle in the vicinity of the proposed alignment; therefore we have shown this boring on the Site Plan (Plate 1) and have included the boring log in Appendix A.

Subsurface exploration as part of the current investigation consisted of drilling 15 soil borings along the proposed base and alternate alignments. Borings B-01 to B-06 were located to provide information for potential pipe-jacking or other culvert installation methods under I-80 and the UPRR. Borings B-09 and B-10 were selected to obtain subsurface information within and under the East Greg Street embankment. The remaining boring locations were planned at roughly uniform spacings along the alignment. All locations were modified as necessary based on considerations of site access.

The soil borings were drilled using a Mobile B-57 truck-mounted drill rig and a CME-55 track-mounted drill rig. All borings were advanced using 8-inch outer-diameter (O.D.), 4.25-inch-inside-diameter (I.D.) hollow stem augers. Due to the amount of time necessary to obtain right-of-entry notices for locations on private property and the UPRR right-of-way, the soil borings were drilled in two mobilizations. Soil borings B-01



through B-03, B-05, B-10, and B-11 were drilled on April 8 and 9, 2009. Soil borings B-04, B-06 through B-09, and B-12 through B-15 were drilled between June 30 and July 2, 2009. Soil borings ranged from 16½ to 46½ feet depth below the existing ground surface.

The locations of the field explorations are shown on the Site Plan, Plate 1. All boring locations were surveyed after completion by Bigby and Associates to obtain horizontal and vertical coordinates within 0.1 foot. Table 1 provides a summary of boring coordinates and elevations. All coordinates and elevations in this report are provided in NAD83 and NAVD88.

TABLE 1 - BORING COORDINATES1

Boring	Elevation (feet)	Easting (feet)	Northing (feet)
B-01	4,393.6	2,306,747.7	14,867,863.8
B-02	4,397.0	2,306,952.5	14,867,654.3
B-03 (MW)	4,395.3	2,307,659.6	14,867,700.0
B-04	4,387.6	2,306,665.3	14,867,524.2
B-05	4,396.9	2,307,610.3	14,867,555.0
B-06	4,389.5	2,307,569.7	14,867,336.5
B-07 (MW)	4,398.2	2,308,199.2	14,867,223.3
B-08	4,393.2	2,308,820.3	14,867,134.5
B-09	4,423.3	2,309,874.5	14,866,679.1
B-10	4,410.4	2,309,766.9	14,866,327.7
B-11 (MW)	4,389.9	2,310,738.8	14,865,844.3
B-12	4,397.9	2,310,525.7	14,866,540.5
B-13	4,397.4	2,311,252.1	14,866,240.1
B-14	4,391.5	2,312,002.0	14,865,867.8
B-15	4,837.8	2,312,313.4	14,865,700.4

Note:

1) Boring locations surveyed by Bigby and Associates relative to NAD83 and NAVD 88.

Samples were taken at 5-foot intervals above and below the approximate depth of invert of the proposed RCB, and at 2½-foot intervals within the approximate top and bottom depths of the RCB. Soil samples were obtained by driving a 2½-inch I.D., 3-inch O.D. California Sampler containing thin brass or steel liners or a 1-3/8-inch I.D., 2-inch O.D. Standard Penetration Sampler. The Mobile B-57 drill rig was equipped with an automatic hammer and the CME 55 was equipped with a cathead hammer. Both hammers weighed 140-pounds and were operated with a normal drop of 30 inches.



The number of blows required to drive the last 12 inches of an 18-inch drive is recorded as the penetration resistance (Blows per foot) on the boring logs. When the sampler was withdrawn from the boring, the liners containing the samples were removed, examined for logging, labeled, and sealed to preserve the natural moisture content for laboratory testing.

A Kleinfelder field engineer logged the soil conditions exposed in the soil borings and collected the bulk and driven samples for laboratory testing. Our engineer also performed on site testing at selected locations in order to evaluate soil strength and consistency. On site testing performed included Standard Penetration Tests (SPT) and undrained shear strength measurements using a pocket penetrometer. The results of the on site testing are presented on the soil boring logs.

Soil conditions encountered are presented on the logs of boring which are included as Plates 2 through 16. A description of the Unified Soil Classification System and a legend of boring log symbols are presented on Plates 17 and 18.

After the soil borings were completed, borings in Nevada Department of Transportation (NDOT) right-of-way (B-1, B-2, and B-5) and in the East Greg Street embankment (B-9 and B-10) were grouted. Borings B-3, B-7, and B-11 were converted to monitoring wells after completion; all other borings (B-4, B-6, B-8, B-10, and B-12 through B-15) were backfilled with excavated soil. Backfill was loosely placed and <u>not</u> compacted to the requirements typically specified for engineered fill.

#### 2.3 Monitoring Wells

Monitoring wells were constructed in three of the soil borings, B-3 (MW), B-7 (MW) and B-11 (MW) for the purpose of evaluating groundwater levels. Wells varied from 25 to 33.5 feet deep with the screened interval extending from the bottom of the well to 5 to 10 feet below ground surface. Blank well casing was used in the top 5 to 10 feet. Details of well construction are shown on the respective boring logs. The monitoring wells must eventually be abandoned in accordance with state regulations during or prior to construction of the NTD by the Owner.



#### 2.4 Laboratory Testing

Laboratory testing is useful for evaluating both index and engineering properties of soils. Typical index tests evaluate soil moisture content, unit weight, soil particle gradation, and plasticity characteristics. Tests for engineering properties can assess soil strength, compressibility, and swell potential. We performed laboratory testing on selected soil samples to assess the following:

- Soil Classification (ASTM D422 and D4318)
- Unit Weight and Moisture Content (ASTM D2937 and D2216)
- Consolidation (ASTM D2435)
- Direct Shear Strength (ASTM D3080)

Gradation and plasticity tests were performed to evaluate the potential re-use of excavated soils as structural fill or backfill, identify the OSHA material classification for excavations, and to provide information for dewatering purposes. Three consolidation tests were used for settlement calculations for the RCBs. Six direct shear tests were performed to assess lateral loads, slope stability, and provide information for temporary, excavation slopes and shoring.

In addition, the following analytical tests were performed by Western Environmental Testing (WET) Laboratory:

- Soluble Sulfate Content
- Resistivity and pH

Individual laboratory test results can be found summarized on the field exploration logs with detailed results on Plates 19 through 30, and in Appendix B at the end of this report.

### KLEINFELDER Bright People. Right Solutions.

#### 3. DISCUSSION

#### 3.1 Regional Geology and Faulting

The site is located in the transition area between the Sierra Nevada geologic province to the west and the Basin and Range geologic province to the east. The site lies within the eastern edge of the Truckee Meadows, a fault-bounded sedimentary basin underlying Reno and Sparks, which is bounded by the Carson Range to the west and the Pah-Rah and Virginia Ranges to the east. Basin and range faulting uplifted these ranges and depressed the valleys starting during Tertiary time, with these movements continuing to the present.

The Truckee Meadows and Truckee River have been greatly influenced by flooding particularly during past glacial periods, with the most recent glacial period, the Tahoe glaciation, most directly influencing near-surface deposits. Torrential glacial floods have resulted in house-size boulders present in outwash deposits under downtown Reno upstream to the west, and resulted in the (confirmed largest grain size in our investigation) gravel- to cobble-sized Tahoe Outwash soils under the North Truckee Drain site on the eastern (downstream) edge of the basin. Boulders are also likely present. With the advent of a warmer, drier climate, the volume and size distribution of sediment transported was greatly reduced, and the sedimentation process became largely limited to the reworking of earlier deposits. Prior to filling, much of this area would develop into a large lake during floods at least once every 1 or 2 decades (USACE, 1970), resulting in deposition of primarily fine-grained (clay and silt) sediments.

According to the *Geologic Map of the Vista Quadrangle* (Bell and Bonham, 1987), no faults have been mapped crossing the project site. Based on review of the *Quaternary Fault and Fold Database for the United States* by the U.S. Geological Survey and the Nevada Bureau of Mines and Geology (2006), the nearest mapped active fault (younger than 15,000 years) is a splay of the unnamed fault zone east of Reno located approximately 3.3 miles to the north of the project site. Therefore it is our opinion that



the potential for ground rupture on known mapped Holocene or Quaternary faults at the site is low.

The nearest mapped fault is a splay of the unnamed north-south-trending fault zone approximately 0.2 mile to the north of Larkin Circle (Bell and Bonham, 1987, USGS, 2006). This fault crosses a lower alluvial fan slope along the abrupt western front of the Pah Rah range and the eastern edge of the Truckee Meadows. While Holocene movement of this fault has apparently not occurred or has not been noted, steady uplift of the Pahrah Range/subsidence of the Truckee Meadows must occur on this fault zone over geologic time to allow greater than 600 to 1,000 feet thickness of Quaternary infill of the Truckee Meadows bedrock basin relative to the bedrock sills of the Truckee River Canyon (Gates & Watters, 1992; Lowe, 2001).

The Truckee River near the east end of the project encounters bedrock at the Vista Narrows. The Vista Narrows is a bedrock ridge that is largely buried in the deep alluvium of the Truckee Meadows but that intercepts the ground surface and restricts down cutting of the Truckee River. This and several other bedrock ridges south of the NTD alignment were reduced in elevation and extent by blasting and excavation in the 1950's in order to improve flood flows out of the Truckee Meadows. As seen on Plate 1, a remaining portion of one of the bedrock areas still creates a constriction to the flow of the Truckee River near the planned NTD outfall. The presence of the bedrock ridges, including a former hill (noted below) near Sparks Boulevard and Brierley Way, suggests that the Pahrah range-front fault could be buried under Truckee Meadows alluvium well west of the present day topographic edge of the range.

The project site lies within the zone of influence of numerous fault systems in western Nevada and eastern California. Should a seismic event occur along any of the nearby faults or fault systems, the site could be significantly affected by ground shaking.

#### 3.1.1 Seismic Design Parameters

The site is located in Sparks, Nevada, which has adopted the 2006 International Building Code (IBC) as the building design standard. If seismic loadings are evaluated using the 2006 International Building Code (IBC) method, we recommend using the following:



- Site Class: D (Applicable to a stiff soil profile with an average shear wave velocity of 600 to 1,200 feet per second and blow counts between 15 and 50) (Table 1613.5.2))
- Mapped Spectral Response Acceleration at Short Periods (S<sub>S</sub>): 1.41g (Figure 1613.5(3))
- Mapped Spectral Response Acceleration at 1-Second Period (S<sub>1</sub>): 0.53g (Figure 1613.5(4))

The spectral response accelerations were obtained from the soil borings performed on site and the USGS *Seismic Design Values for Buildings*, Java Ground Motion Parameter Calculator-Version 5.08 for the location of 39.5248° Latitude and -119.7017° Longitude.

#### 3.2 Site Geology

Information presented on the *Geologic Map of the Vista Quadrangle* (Bell and Bonham, 1987) indicates the site area is underlain by Floodplain deposits of the Truckee River (Qfl) of the Holocene era. The map describes this deposit as "light gray to dark gray brown sit, sandy silt, and clayey silt with local lenses of well rounded pebble to cobble gravel derived from mainstream and overbank deposition by the Truckee River." Locally much of this area prior to development was subject to periodic flooding from the Truckee River. Most of the surface natural deposits in the proposed alignment are expected to be fine-grained silt or clay deposits.

The floodplain deposits are underlain by very dense, Pleistocene-age Tahoe Outwash (Qto) deposits described as "gray, sandy, cobble to boulder gravel with lenses of light brown to light gray medium sand and light gray clayey silt." For the purposes of this investigation Tahoe Outwash deposits are characterized as dense to very dense poorly graded sands and gravels with the likely presence of cobbles and boulders. The Tahoe Outwash deposits can generally be characterized as high permeability soils.

#### 3.3 Site Conditions

Access to the project site is provided by various paved and gravel roadways and through private property. The northern portion of the property (north of Interstate 80)



consists of roadways along Brierley Way and the I-80 westbound off ramp to Sparks Boulevard. Areas adjacent to the freeway ramp and Brierley Way are landscaped with low to moderate-height shrubs.

Prior to 1968, a 45-foot high hill stood above the surrounding floodplain north of Brierley Way on the east side of the NTD, at the northwest extent of the project alignment (see Plate 1). This hill was likely excavated as a borrow source for development of the adjacent areas (USACE, 1970).

The freeway and railroad are on raised embankments above the surrounding terrain. There is typically a depression between I-80 and the railroad mainline. There is also typically a depressed corridor between the UPRR mainline embankment and the industrial properties to the south which are on fill. Both depressed areas have low to moderate-height brushy vegetation, including sage brush, willows, and weeds. Regional utilities (gas pipelines and fiber optic cables) are suspected along either side of the railroad but have not been investigated by Kleinfelder in detail.

South of Interstate 80 and the UPRR tracks the proposed alignment runs west through vegetated undeveloped right-of-way and industrial properties. A portion of the alignment traverses adjacent to and partially in the existing NTD channel. The proposed alignment crosses through the East Greg Street embankment then traverses under Larkin Circle to a short levee before discharging into the Truckee River. Specific discussions on the proposed construction adjacent to the existing NTD channel, through the East Greg Street embankment, and through the existing levee are addressed in Section 5.12.

#### 3.4 Subsurface Conditions

The following paragraphs provide brief general summaries of the results of our field explorations for the proposed project. The boring logs, presented in Appendix A, should be reviewed for a more detailed description of the subsurface conditions at the locations explored. The stratification lines shown on the borings logs are inferred boundaries between soil types, and the actual transition may be gradual. Due to the nature and depositional characteristics of the native soils, care should be taken in interpolating and extrapolating subsurface conditions between and beyond the boring locations.



#### 3.4.1 Fill

Most of the developed portions of the alignment including all roadways and industrial areas are likely on fill. The encountered fill was generally granular material, consisting of clayey or silty sands or gravels. It is likely cobbles and boulders are also present in the fill. It should be expected that fill material under Interstate 80, the UPRR tracks, East Greg Street embankment, Larkin Circle, within the levee, and in industrial yards will be of greatly varying material due to the different years of construction, potential fill sources, and level of care associated with their construction.

Research was not performed to assess whether the encountered fills were properly compacted or documented as structural fill; therefore, apparent densities of the encountered fill material have not been provided on the soil boring logs. Deeper and/or poorer quality fill in other areas of the alignment beyond our explorations could be present and should be anticipated.

The bottom of fill was generally interpreted based on encountering the top of the underlying soft to stiff fine-grained alluvial, floodplain soils. The interpreted thickness and approximate elevation of bottom of fill encountered during this investigation are presented in Table 2, below.



TABLE 2
SUMMARY OF ENCOUNTERED FILL THICKNESS AND ELEVATIONS

Boring Number	General Location	Elevation of Boring (feet) <sup>1</sup>	Approximate Depth of Fill (feet) <sup>2</sup>	Approximate Elevation of Bottom of Fill (feet) <sup>2</sup>	
B-01	Interstate 80 off ramp	4,393.6	8 ½	4385	
B-02	Interstate 80	4,397.0	12 ½	4384.5	
B-03 (MW)	Briery Way	4,395.3	10	4385	
B-04	People's Drain	4,387.6	0	4388	
B-05	Interstate 80	4,396.9	10 ½	4386.5	
B-06	Existing NTD channel	4,389.5	5	4385	
B-07 (MW)	Washoe County School District	4,398.2	14	4384	
B-08 B-09	UPRR ROW  East Greg Street  Embankment	4,393.2	6 30 ½	4387 4393	
East Greg Street B-10 Embankment		4,410.4	26	4384.5	
B-11 (MW)	Larkin Circle	4,389.9	4	4386	
B-12 UPRR ROW		4,397.9	4	4394	
B-13	UPRR ROW	4,397.4	4	4393.5	
B-14	UPRR ROW	4,391.5	0	4391.5	
B-15 UPRR ROW		4,387.8	0	4388	

Notes: 1) Boring elevations provided by Bigby and Associates in NAVD 88.

#### 3.4.2 Native Material

The native soils along the alignment generally consisted of flood-plain clays and silts underlain by Tahoe Outwash sands and gravels, except at the northwest end of the alignment near Brierley Way, and at the eastern portion along Larkin Circle.

The floodplain clays and silts were generally soft to very stiff, moderate- to high-plasticity, and contained some fine and medium sized sand. Occasionally gravel or possible cobbles were encountered which resulted in unrepresentatively high blow counts for this material. East of the East Greg Street embankment under Larkin Circle, the flood-plain deposits appear to be more consistently silty sand, poorly-graded sand with silt, or sandy silt (borings B-11 through B-15), possibly because the river gradients

<sup>2)</sup> Depths of fill and elevations to bottom of fill are rounded to nearest ½ foot due to measurement methods.



and velocities increased towards the outlet of the flood-plain into the mouth of the Truckee Canyon. Aerial photographs prior to development (USACE, 1970) indicate a number of flood-level river channels or drainages converging on the mouth of the Truckee Canyon underlying the vicinity of Larkin Circle.

The fill and floodplain deposits are generally underlain by the Tahoe Outwash, the approximate depths and elevations of the outwash deposits encountered in the borings are summarized in Table 3, below. Sands and gravels of the Tahoe Outwash were generally very dense with low to moderate content of non-plastic fines. Interbedded sand and clay layers were noted at 3 to 6 inch intervals in the outwash deposits in some borings, specifically B-07 and B-08. Boulders, cobbles, and/or coarse gravel are likely present in some locations based on locally-difficult drilling. The base of the floodplain deposits was not encountered at boring B-06 which extended through clays and sandy clays to 4,363 feet, the maximum depth explored. Dense outwash deposits were also not encountered in the borings B-13 through B-15.



TABLE 3
SUMMARY OF TAHOE OUTWASH DEPTHS AND ELEVATIONS

Boring Number	General Location	Elevation of Boring (feet) <sup>1</sup>	Approximate Depth to Outwash Deposits (feet) <sup>2</sup>	Approximate Elevation of Outwash Deposits (feet) <sup>2</sup>
B-01	Interstate 80 off ramp	4,393.6	19 ½	4374
B-02	Interstate 80	4,397.0	24	4373
B-03 (MW)	Brierley Way	4,395.3	18 ½	4377
B-04	People's Drain	4,387.6	16	4371.5
B-05	Interstate 80	4,396.9	29	4368
B-06	Existing NTD channel	4,389.5	>26 ½ 3	<4363 <sup>3</sup>
B-07 (MW) Washoe County School District		4,398.2	23	4375
B-08	UPRR ROW	4,393.2	18 ½	4374.5
B-09	B-09 East Greg Street Embankment		46	4377.5
B-10 East Greg Street Embankment		4,410.4	33	4377.5
B-11 (MW)	B-11 (MW) Larkin Circle		23	4367
B-12	B-12 UPRR ROW		15	4383
B-13	B-13 UPRR ROW		>30 ½ <sup>3</sup>	<4367 <sup>3</sup>
B-14	UPRR ROW	4,391.5	>26 ½ <sup>3</sup>	<4365 <sup>3</sup>
B-15 UPRR ROW		4,387.8	>16 ½ <sup>3</sup>	<4371.5 <sup>3</sup>

Notes: 1) Boring elevations provided by Bigby and Associates in NAVD 88.

In Borings B-03 and B-05, brown to purple-brown clayey gravel to clayey sand was present below the fill which is likely soil and weathered bedrock materials present from the former hill on the north side of Brierley Way. The extent of this material was not determined further.

Significant thickness of the outwash deposits throughout the project site, and sandy floodplain deposits (under Larkin Circle) will likely have very high permeability. Heaving sands were encountered at a depth of 24 feet in soil boring B-1 and lower blow counts were observed near the top of the sands and gravels. These conditions can be the result of concentrated seepage towards the boring excavations as discussed in the following section.

<sup>2)</sup> Depths and elevations are rounded to nearest ½ foot due to measurement methods.

<sup>3)</sup> Outwash deposits were not encountered to the maximum depth explored.



#### 3.4.3 Groundwater

Groundwater was encountered in all soil borings, except B-13, and ranged in elevations of approximately 4,371 to 4,381 feet, with higher groundwater elevations typically in the western (upriver) portions of the project. Table 4, below, summarizes the approximate groundwater depths and elevations at the locations where groundwater was first encountered and stabilized groundwater elevation was recorded if the boring was maintained open long enough for the levels to stabilize. It is possible that variations in groundwater elevation and moisture content may occur due to seasonal changes, runoff, precipitation, construction activities, and/or other factors.

In general, free standing groundwater was initially encountered within the borings near the top of the Tahoe Outwash. Once the lower permeability clays and fills were penetrated, the free standing groundwater rose within the bore holes. This is suggestive of an artesian condition.

Groundwater elevations from various dates taken from the three monitoring wells are also summarized in the table. Kleinfelder will continue to monitor the groundwater wells on at least a quarterly basis and will provide a summary letter upon completion of one year of groundwater measurements. These monitoring wells must be abandoned in accordance with Nevada regulations prior to or during construction; it is the Owner's responsibility to ensure these wells are abandoned.



# TABLE 4 SUMMARY OF GROUNDWATER DEPTHS AND ELEVATIONS

Boring Number	General Location	Elevation of Boring (feet) <sup>1</sup>	Approximate Depth to Initial Ground- water (feet) <sup>2</sup>	Approximate Elevation of Initial Ground- water (feet) <sup>2</sup>	Approximate Depth to Stabilized Ground- water (feet)	Approximate Elevation of Stabilized Ground- water (feet) <sup>2</sup>
B-01	Interstate 80 off ramp	4,393.6	19	4374.5	17	4376.5
B-02	Interstate 80	4,397.0	25	4372	15.5	4381.5
					19.0 (4/8/2009)	4,376.0
B-03	Driewley May	4 205 2	10	4376.5	13.9 (6/18/2009)	4,381.4
(MW)	Brierley Way	4,395.3	19	4376.5	14.1 (7/20/2009)	4,381.2
			:		13.8 (11/10/2009)	4,381.5
B-04	People's Drain	4,387.6	7 ½	4380	NA	-
B-05	Interstate 80	4,396.9	20	4377	16 ½	4380.5
B-06	Existing NTD channel	4,389.5	11	4378.5	NA	
	Washoe				17.3 (7/2/2009)	4380.9
B-07	County	4,398.2	23	4375	17.8 (7/20/2009)	4380.4
(MW)	School District	,			17.45 (11/10/2009)	4380.7
B-08	UPRR ROW	4,393.2	15	4378	NA	-
B-09	East Greg Street Embankment	4,423.3	45	4378	NA	-
B-10	East Greg Street Embankment	4,410.4	34 ½	4376	34 ½	4376
					14.5 (4/8/2009)	4,375.4
B-11	Lorkin Cirolo	4 290 0	141/	4375.5	12.3 (6/18/2009)	4.377.6
(MW)	Larkin Circle	4,389.9	14 ½	4375.5	13.2 (7/20/2009)	4.376.7
					13.6 (11/10/2009)	4376.3
B-12	UPRR ROW	4,397.9	17	4381	17	4381
B-13	UPRR ROW	4,397.4	>30 ½ 3	< 4367 <sup>3</sup>	NA	-
B-14	UPRR ROW	4,391.5	16	4375.5	NA	-
B-15	UPRR ROW	4,387.8	16 ½	4371 ½	NA	-

Notes: 1) Boring elevations provided by Bigby and Associates in NAVD 88.

<sup>2)</sup> Depths and elevations are rounded to nearest ½ foot due to measurement methods unless otherwise noted.

<sup>3)</sup> Groundwater was not encountered to the maximum depth explored.



Long-term groundwater level records were obtained from the Washoe County School District property, located North of Kleppe Lane and approximately south of boring B-7. The south-central portion of this property was instrumented with 12 monitoring wells, as summarized in Broadbent & Associates, (2008); a site plan and data tables from this report are included in Appendix C. Groundwater data from 1999 to 2008 for the four wells closest to the proposed NTD alignment are summarized on Plate 31. Readings from monitoring well B-07(MW) installed on this project have been appended to the previous results and show readings which are consistent with median trends for the previous monitoring wells.

The Broadbent & Associates report (2008) does not indicate the method used to determine the elevation and exact location of the monitoring wells. It should be noted that the groundwater elevation has varied up to 5 feet over a six-year time period (excluding a reading in January 2008 which is assumed to be incorrect and has been removed), primarily during wet winter seasons. Based on conversations with Mr. John Nolan of the Washoe County School District, the monitoring wells were abandoned after January 2008.

#### 3.5 <u>Liquefaction</u>

A quantitative liquefaction analyses was outside the scope of this project and has therefore not been performed. Qualitative discussion is provided below based on Kleinfelder's experience in the area and encountered subsurface material to limited depths.

Liquefaction is a nearly completed loss of soil shear strength that can occur during a seismic event in saturated, loose to medium dense, poorly-graded sands, silty sands, cohesionless silts, and some gravels. Liquefaction results from cyclic shear stresses and strains causing partial collapse of the soil matrix and development of excessive pore water pressure between the soil grains. Liquefaction will result in settlements shortly after the earthquake. Water and sand may be expelled to the surface, referred to as sand boils; these may cause minimal damage, except if building footings are located directly over a major sand boil. For sites with gentle or minimal slopes or with an adjacent slope, significant damage may potentially result from ground oscillation or lateral spreading. Uplift can occur to buried structures which are less dense than the surrounding soil.



Based on the depth of groundwater and the presence of plastic clays over dense Tahoe Outwash deposits, liquefaction potential for most of the project alignment is expected to be negligible.

East of East Greg Street, medium dense sands are present, with negligible fines contents, which are at least 8 feet thick below the groundwater table. The low blow counts near the top of these soil layers suggest these soils may potentially liquefy during a design-level earthquake; however, it is our professional opinion the low blow counts are due to the drilling method and the likely artesian condition in the borings at the contact between the floodplain and outwash deposits. The hollow stem drilling method that was used has been known to result in lower blow counts than the standard field methods for liquefaction analysis (i.e. rotary wash). Based on the preliminary information, it is our opinion the likelihood of liquefaction during a design-level earthquake is low.



#### 4. CONCLUSIONS

The following conclusions are based on the data collected during this assessment and are subject to the limitations stated in this report. These conclusions may change if additional information becomes available. Based on the results of our study, no severe soil or groundwater constraints were observed which would preclude development. The following is a summary of our conclusions.

Most of the proposed RCB alignment is located several feet below the groundwater table as measured in this investigation, and about one third to half of the alignment is located over soft to stiff clays. These saturated soils will be difficult to prepare for RCB subgrade, and therefore extensive use of stabilizing fill under the box culverts will generally be required. Excavated fill materials will generally be re-usable as structural fill (likely with some processing); however the 5 to 10 feet of clay in the excavations will have limited potential for re-use.

Extensive dewatering will be required to maintain a relatively dry excavation to allow for construction of the RCB. Dewatering and subgrade preparation requirements may be less stringent where pre-cast concrete segments can be put in place rather than using cast-in-place concrete. Use of drain rock stabilizing fill may assist in removing groundwater in addition to other methods such as wells or sumps. The dewatering system shall be designed by the contractor. The contractor may need to shore excavations to compensate for limited construction easement width.

Specific recommendations and specifications for project design and construction including mitigation of potential problems described above are presented in Section 5.0. A summary table including the boring location, elevation of boring, proposed bottom of RCB, depth of fill, elevation of outwash deposits, and elevation of initial groundwater measurements are included in Table 5, below.



# TABLE 5 SUMMARY OF ENCOUNTERED SUBSURFACE CONDITIONS AND ELEVATION OF RCB

Boring Number	General Location	Elevation of Boring (feet) <sup>1</sup>	Approximate Elevation of Bottom of RCB (feet) <sup>2</sup>	Approximate Depth/ Elevation of Fill (feet) <sup>3</sup>	Approximate Elevation of Initial Groundwater (feet) <sup>3</sup>	Approximate Elevation of Outwash Deposits (feet) <sup>3, 5</sup>
B-01	Interstate 80 off ramp	4,393.6	4,385.5	8 ½ / 4,385	4,374.5	4,374
B-02	Interstate 80	4,397.0	4,382	12 ½ / 4,384.5	4,372	4,373
B-03 (MW)	Brierley Way	4,395.3	-	10 / 4,385	4,376.5	NE⁴
B-04	People's Drain	4,387.6	4,379	0 / 4,387.5	4,380	4,371.5
B-05	Interstate 80	4,396.9	-	10 ½ / 4,386.5	4,377	4,368
B-06	Existing NTD channel	4,389.5	4,378	5 / 4,384.5	4,378.5	NE⁴
B-07 (MW)	Washoe County School District	4,398.2	4,377	14 / 4,384	4,375	4,375
B-08	UPRR ROW	4,393.2	4,377	6 / 4,397	4,378	4,374.5
B-09	East Greg Street	4,423.3	-	30 ½ / 4,393	4,378	4,377.5
B-10	East Greg Street	4,410.4	4,376.5	26 / 4,384.5	4,376	4,377.5
B-11 (MW)	Larkin Circle	4,389.9	4,376	4 / 4,386	4,375.5	4,367
B-12	UPRR ROW	4,397.9	-	4 / 4,394	4,381	NE <sup>4</sup>
B-13	UPRR ROW	4,397.4	-	4 / 4,393.5	< 4,367 <sup>4</sup>	NE⁴
B-14	UPRR ROW	4,391.5	-	0 / 4,391.5	4,375.5	NE⁴
B-15	UPRR ROW	4,387.8	-	0 / 4,388	4,371 ½	NE⁴

Notes: 1) Boring elevations provided by Bigby and Associates in NAVD 88.

<sup>2)</sup> Elevations from HDR preliminary plans (2009) and are estimated to nearest ½ foot.

<sup>3)</sup> Depths and elevations are rounded to nearest ½ foot due to measurement methods. Groundwater elevations will vary seasonally.

<sup>4)</sup> Not encountered to the maximum depth explored.

<sup>5)</sup> Elevation of Outwash deposits are typically the bottom elevation of the floodplain deposits. Refer to boring logs for more detail.

### KLEINFELDER Bright People. Right Solutions.

#### 5. RECOMMENDATIONS

#### 5.1 General Recommendations

The following sections of this report present our analysis and recommendations regarding site preparation, excavation, earthwork, and box culvert construction, and recommended observation and testing during construction. Prior to performing excavations, the groundwater level should be sufficiently lowered to minimize the likelihood of unstable subgrade conditions. Given the granular nature of the outwash deposits and groundwater levels in the vicinity of the site, significant construction dewatering should be anticipated.

#### 5.2 Site Clearing and Preparation

Prior to construction, all existing improvements (sidewalks, curb and gutter, underground utilities, etc.) will need to be demolished and removed from the site. Bituminous pavements, concrete curb, sidewalks, gutters, and driveways should be removed to neatly sawed edges. Existing asphalt pavements should be disposed of off site or stockpiled and processed for reuse beneath new pavements.

Landscaping areas should be stripped/grubbed of organic soils, tree roots, etc. It appears approximately 4 to 6 inches can be used as a reasonable estimate for average depth of stripping. Deeper stripping/grubbing of organic soils, roots, etc., and potentially removal of debris fill in industrial lot areas may be required locally. Tree root balls should be removed and the resulting voids backfilled with adequately compacted backfill soil.

Existing monitoring wells (installed as part of this investigation) must be abandoned in accordance with Nevada Department of Environmental Protection standards and shall be the responsibility of the Owner. Kleinfelder can perform the abandonment of the monitoring wells if necessary at the Owner's direction.



We understand that the existing footings for the UPRR bridge crossing over the North Truckee Drain will be cut in order to provide greater lateral clearance for the proposed box culvert. This bridge presently may be supported by spread footings or pile foundations. A structural investigation should be performed to confirm removal of the toe of the footings will not cause distress or failure.

The Geotechnical Engineer should be present during demolition and site preparation to observe stripping and grubbing depths. Dust control should be the responsibility of the Contractor.

#### 5.3 Earthwork

Where import fill is necessary, materials should meet the gradation and plasticity requirements listed for "structural fill" based on the Standard Specification for Public Works (2007, Section 200.01.09) except for reconstruction of the levee at the east end of the project. These specifications include requirements including but not limited to a maximum particle size of one inch, between 5 and 20 percent of materials passing the No. 200 sieve, and a liquid limit of 35 maximum and a plastic limit of 12 maximum. It appears that some of the existing site fills or Tahoe Outwash soils may be capable of meeting recommended requirements for structural fill, with some processing.

Structural fills used to backfill over the culvert in the East Greg Street embankment should also have an R-value of 45 or greater to meet NDOT requirements. We have assumed that the existing material in the East Greg Street embankment may be re-used to reconstruct the embankment.

The floodplain deposits are unsuitable for structural fill and should be exported off site or used only in non-structural fills. However, one exception is that the floodplain deposits may be reused as structural fill above the RCB assuming that no permanent improvements except industrial yards or pavements are planned above the box culvert. These soils should be compacted to 90 percent relative density and above optimum moisture content as determined by ASTM D1557 and at least three feet of structural fill is placed above the floodplain soils.

Fill within structural areas and backfill over and around box culverts should be placed in maximum 8-inch-thick (loose) lifts, each densified to, at least, 90 percent relative



compaction (ASTM D1557). In all cases, the finished surface should be smooth, firm, and show no signs of deflection. Grading should not be performed with or on frozen soils.

#### 5.4 Subgrade Preparation and Subgrade Stabilization

Subgrade preparation requirements (remedial earthwork) differ for three separate conditions: subgrade for pre-cast RCB placement, subgrade for cast-in-place RCB, and subgrade for near-surface improvements that will be founded less than 5 feet below final grade. In many cases, the requirement for subgrade preparation will be superceded by the requirement to provide a stable subgrade for construction (i.e., subgrade stabilization). The methods described below are contingent upon adequate groundwater control, as discussed in Section 5.6

Clay soils were found to exist from the ground surface down to or below the planned RCB invert at most boring locations. Where clay is not present, saturated granular soils are present with groundwater present at or above the planned RCB invert. Either of these soil conditions may require stabilization. Prior to excavation, the groundwater should be sufficiently lowered to prevent unstable conditions. Light, track-mounted construction equipment should be used in excavations to help prevent destabilizing the subgrade soils and causing "pumping". In the event unstable soils are encountered in the excavation bottoms, additional construction dewatering, overexcavation and/or subgrade stabilization would be necessary.

#### 5.4.1 Subgrade Stabilization

For preparation of the box culvert subgrade and for any construction that may be performed during wet weather, the subgrade soils will most likely be well above optimum moisture content and difficult to impossible to compact. In some situations, moisture conditioning of the top 12 inches of subgrade may allow the soil to dry sufficiently to allow compaction. Where construction schedules preclude delays or drying is ineffective, mechanical subgrade stabilization will be necessary. Subgrade stabilization is usually a trial and error process, typically determined with a test section. Two potential mitigation options are discussed here. The final selection of a method of stabilization and final subgrade stabilization is the contractor's responsibility.



For cast-in-place RCB construction, mechanical stabilization may be achieved by over-excavation and/or placement of an initial 12- to 18-inch-thick lift of 12-inch-minus, 3-inch-plus, well graded, angular rock fill. The more angular and well graded the rock is, the more effective it will be. This fill should be densified with large equipment, such as a self-propelled sheeps-foot or a large loader, until no further deflection is noted. Additional lifts of rock may be necessary to achieve adequate stability. A leveling course of on average 6 inches of drain rock or aggregate base could be placed over the rock fill to allow for fine grading of the RCB footprint.

For preparation of subgrade particularly for pre-cast culvert sections, a greater thickness of drain rock underlain by a reinforcing geotextile could be considered. A moderate strength geotextile, such as Mirafi 180N, Mirafi S800, or equal, would be placed in the range of 24 inches below planned subgrade, and would be covered with drain rock (Class C or D backfill, Standard Specifications Section 200.03, 2007). The drain rock bedding would ease minor grade adjustments during RCB placement, and could potentially provide a supplemental drain material for groundwater removal.

If the stabilizing fill is intended to support extensive vehicular traffic, additional geotextile strength and/or fill thickness may be required. The contract documents should provide flexibility for additional subgrade stabilization and overexcavation of as needed during grading operations.

#### 5.4.2 Pre-Cast RCB Construction

Pre-cast RCBs founded at least 5 feet below final grade may be constructed on the native clay soils or other native subgrade, provided a working surface can be established. Clays should not be allowed to dry out prior to backfilling. In order to facilitate leveling of subgrade under the RCB, it is common to place a granular leveling course such as 6 to 12 inches of drain rock under the precast segments that can be easily leveled. This leveling course will also assist in maintaining moisture conditions of underlying clays where present. Aggregate base or pit-run sand should not be used for leveling because it will tend to become unstable and pump once it is saturated. This approach assumes that the subgrade for the RCB will not be subject to heavy or repeated loads. If excess movement (pumping) of subgrade occurs during placement of the drain rock (Class C or D backfill, Standard Specifications Section 200.03, 2007), mechanical stabilization should first be used.



#### 5.4.3 Cast-in-Place RCB Construction

Cast-in-place RCB segments founded at least 5 feet below native grade (except for connector segments less than 10 feet long joining adjacent pre-cast segments, which can use the criteria for pre-cast segments) may be founded on existing clay or native subgrade, provided that a working surface can be established, and the top 6 inches of subgrade can be densified to at least 90 percent relative compaction relative to ASTM D 1557. Granular soils should be within 2 percent of optimum moisture content, and clays should be at or above optimum moisture content. Where these conditions cannot be achieved, mechanical subgrade stabilization should first be used.

#### 5.4.4 Improvements Founded Near Final Grade

Clay soils were classified as moist to wet, soft to very stiff, and as exhibiting low to high plasticity, and therefore have potential for shrink-swell movement when subject to seasonal moisture changes. For structures or other improvements that are founded within 5 feet of final grade, the structure should be separated from clays or silts by a minimum of 2 feet of structural fill (as defined in Section 5.3). These structures may potentially include wing walls footings, outlet and inlet structures and slabs, any portion of the RCB with less than 5 feet of cover to foundation level, maintenance buildings, and new pavements.

Prior to structural fill placement, the exposed subgrade surfaces at the base of the 2 feet of separation should be scarified to a minimum depth of six inches, moisture conditioned as necessary, and compacted to a minimum of 90% relative compaction in accordance with the ASTM D1557 compaction test method. A minimum of 90% relative compaction in accordance with the ASTM D1557 compaction test method is also recommended for the structural fill required for separation. Where less than 70 percent passes the 3/4-inch sieve, subgrade soils are too coarse for standard density testing techniques. In this case, as will likely occur on Tahoe Outwash soils, proof rolling is recommended. For bidding purposes, we assume that proof-rolling often can be achieved a minimum of five single passes with a minimum 10-ton roller in mass grading, or five complete passes with hand compactors in footing trenches, however the exact procedure will have to be determined by the contractor and inspector in the field. Proof-rolling has proved to provide adequate project performance for coarse-grained soils, as



long as all other geotechnical recommendations are closely followed. In all cases, the final surface should be smooth, firm, and exhibit no signs of deflection.

Clay subgrade to be left in place and covered with fill should be moisture-conditioned to at or over optimum for a minimum depth of 12 inches. This moisture level will significantly decrease the magnitude of shrink-swell movements in the upper foot of clay. The high moisture content must be maintained by periodic surface wetting, or other methods, until the surface is covered by at least one lift of fill. If allowed to dry out, subsequent expansion of clay soils could results in differential heave or settlement of improvements.

#### 5.5 Trenching and Excavation

We expect that all materials can be excavated with conventional earthmoving equipment, e.g. bulldozers and excavators. The contractor should be aware cobbles and boulders are likely present in the subsurface soils and the contractor should be prepared to handle this size material.

Most of the project is underlain by firm to stiff clays which extend from approximately the top to midheight of the planned culvert to at or below the box culvert invert (See Table 5). Therefore while trucks, scrapers, or other wheeled equipment could be supported along haul roads near original ground surface, excavation below the surface fill would be expected to require track-mounted excavators. Excavation operations should be performed in a manner so as to minimize disturbance of clays which can decrease bearing capacity and increase settlements. Subgrade stabilization may be required for construction on the fine grained material and is discussed further in Section 5.4.

#### 5.6 Construction Dewatering

Groundwater is expected to be encountered in excavations (see Table 4). Fluctuations in the level of the groundwater and soil moisture conditions as noted in this report may occur due to variations in precipitation, land use, irrigation, snow melt, river levels, and other factors. It should be noted the Broadbent & Associates report showed groundwater levels as high as approximately 4,384.5 feet in June of 2006.



Groundwater should ideally be lowered several feet below the bottom of the excavations to provide a firm, unyielding subgrade for construction and prevent unstable excavation wall conditions. The dewatering system should be a Contractor-designed system. Control of groundwater should be accomplished in such a manner that will preserve the strength of the foundation of soils, not cause instability of any excavated slopes or the nearby existing slopes, and not result in damage to existing structures. The water should be lowered in advance of any excavations by deep wells, well points, or other methods. Open sumps should not be permitted if it results in boils, loss of fines, or unacceptable settlement of existing structures. Water should not be allowed to pool and remain in the excavated area over an extended period of time.

Although 28 gradation tests have been performed, extreme caution should be used in evaluating permeability and dewatering rates based on grain size only, especially in the outwash deposits since larger soil particles cannot be obtained in the soil samples used in this investigation. Excavations into or immediately above the Tahoe Outwash will increase rate of groundwater seepage and likely require more stringent groundwater control methods. It has been Kleinfelder's experience that outwash deposits are highly permeable and significant dewatering should be anticipated.

General lowering of the groundwater can result in surface settlement of nearby structures. This should be taken into account in the Contractor's design of the dewatering system. If well points are used, nearby structures should be monitored for settlement and instability during dewatering operations.

Discharge should be arranged to meet the necessary local governmental requirements and permits and to facilitate sampling by the engineer of record. Potential points of discharge include land disposal, the sanitary sewer system, and the Truckee River. Discharge to the Truckee River will require an NPDES permit from the State of Nevada Division of Environmental Protection may likely require pre-treatment and will require considerable monitoring of the Truckee River and discharge waters.

#### 5.7 Temporary Excavation Slopes

We understand the proposed project will include the installation of RCBs up to 35 feet deep at East Greg Street; however the majority of the project will involve excavations on the order of 15 to 20 feet deep. This section addresses the majority of the excavations



necessary for the proposed project; a specific discussion on the cuts for East Greg Street is addressed in Section 5.12.2. Construction dewatering for excavations below groundwater should be anticipated to lower the groundwater below proposed excavations.

The Contractor is responsible for site safety and all excavations should be evaluated to verify their stability, prior to occupation by construction personnel. We do not expect the walls of excavations in the site fill soils to stand near vertical without sloughing. The Contractor should be prepared to shore or slope excavations in these materials. For the clayey site soils, trench excavations should comply with current OSHA safety requirements (Federal Register 29 CFR, Part 1926) for Type B soil. In the granular soils, including structural fill, excavations will need to be modified to comply with OSHA requirements for Type C soil. Any area in question should be considered Type C, unless specifically examined by the contractor's engineer during construction. Conditions more restrictive than Class C could result if the contractor does not provide adequate groundwater control. All trenching shall be performed and stabilized in accordance with OSHA standards.

Excavations will require shoring or laying back of sidewalls to maintain adequate stability. Regulations amended in Part 1926, Volume 54, Number 209 of the Federal Register (Table B-1, October 31, 1989) requires that temporary sidewall slopes be no greater than those presented in Table 6.



TABLE 6 - MAXIMUM ALLOWABLE TEMPORARY EXCAVATION SLOPES

Soil or Rock Type	Maximum Allowable Slopes <sup>1</sup> for Deep Excavations less than 20 Feet Deep <sup>2</sup>
Stable Rock	Vertical (90 degrees)
Type A <sup>3</sup>	3H:4V (53 degrees)
Type B	1H:1V (45 degrees)
Type C	3H:2V (34 degrees)
	Notes:

- 1. Numbers shown in parentheses next to maximum allowable slopes are angles expressed in degrees from the horizontal. Angles have been rounded off.
- 2. Sloping or benching for excavations greater than 20 feet deep shall be designed by a registered professional engineer.
- 3. A short-term (open 24 hours or less) maximum allowable slope of 1H:2V (63 degrees) is allowed in excavation in Type A soils that are 12 feet or less in depth. Short-term maximum allowable slopes for excavations greater than 12 feet in depth shall be 3H:4V (53 degrees).

The State of Nevada, Department of Industrial Relations, Division of Occupational Safety and Health, has adopted and strictly enforces these regulations, including the classification system and the maximum slopes. In general, Type A soils are cohesive, non-fissured soils, with an unconfined compressive strength of 1.5 tons per square foot (tsf) or greater. Type B are cohesive soils with an unconfined compressive strength between 0.5 and 1.5 tsf. Type C soils have an unconfined compressive strength below 0.5 tsf. Numerous additional factors and exclusions are included in the formal definitions. The client, owner, design engineer, and contractor shall refer to Appendix A and B of Subpart P of the previously referenced Federal Register for complete definitions and requirements on sloping and benching of trench sidewalls. Appendices C through F of Subpart P apply to requirements and methodologies for shoring.

For any temporary slopes, the cut faces should be inspected by the Contractor during the work day for any signs of movement and tension cracks. Workers should not be allowed to work near the excavations unless such inspections deem the area safe. During periods of heavy precipitation, a potential for slough of the cut slope will exist and precautions should be taken. Workers should not work at the toe of the slopes during such storm events. In the event the soils become wet from a storm event, or any other source; work along the toe of the slopes should be halted until the stability of the slopes is reassessed.



During wet weather, runoff water should be prevented from entering excavations. Water should be collected and disposed of outside the construction limits. Heavy construction equipment, building materials, excavated soil, and vehicular traffic should not be allowed within a distance of one-third the slope height from the top of any excavation.

#### 5.8 Shoring

Shoring will be required where space or other restrictions do not allow a sloped construction slope, and where loose fill material is encountered near the surface, or excavations may be shored at the option of the contractor. Layers of cohesionless sands in the outwash deposits should be anticipated that would slough or ravel and would not retain a vertical cut. Soil nailing and walls with ground anchors (tiebacks) have been used successfully for construction excavations within the Reno Valley in similar deposits. Any shoring design (e.g. soil nail, tieback anchor/solider pile, etc.) should consider, among other things: bottom heave/shear failure at/below shoring walls; groundwater inflow in and below shoring; effect of temporary stand-up time in cohesionless soil; flowing sands; presence of cobbles and boulders.

Any shoring system would have to meet OSHA pre-approved configurations or be designed by the Contractor to meet OSHA standards. The contractor should submit details and calculations of any non-standard shoring or excavation support systems to the Owner prior to construction. The shoring system should prevent unacceptable movement or settlement of adjacent structures.

It is understood UPRR has stringent design criteria for any temporary shoring within their ROW. Any proposed shoring within the UPRR ROW must be approved by UPRR. The contractor should refer to "Guidelines for Temporary Shoring", dated October 25, 2004, published by UPRR for additional information.

#### 5.9 Recommended Permanent Slope Angles

We recommend that permanent fill and cut slopes be no steeper than 2H:1V. The East Greg Street embankment may be rebuilt to match the existing slopes which is slightly steeper than 2H:1V provided the embankment uses fill with an R-value of 45 or greater. Satisfactory slope performance is primarily affected by drainage and runoff. Care must



be taken that drainage is not directed to flow over slope faces. Slope faces should be protected against erosion resulting from direct rain impact.

#### 5.10 Foundations

The proposed box culvert will be supported by a concrete mat foundation (i.e. the bottom of the RCB) and may be designed for an allowable soil bearing pressure of 1,500 psf. If the RCBs will be entirely founded on dense outwash deposits or structural fill extending to outwash deposits the allowable bearing capacity may be increased to 3,000 psf.

Other foundations which may be part of this project may include wingwalls, retaining walls, outfall structures, maintenance buildings or temporary loads which will also likely be founded at depths near the top of the clay layers or lower. Foundations designed and constructed in accordance with the recommendations of this geotechnical report may be designed for an allowable soil bearing pressure of 1,500 pounds per square foot for dead loads plus long-term live loads. This assumes a minimum separation of foundations from clays with at least 24 inches of structural fill compacted to 90% relative compaction (ASTM D1557). The allowable soil bearing pressure was calculated using a minimum foundation width of 12 inches and an embedment depth of 12 inches.

The allowable bearing pressure value may be increased by one-third for short-term loading conditions, including temporary wind and seismic forces. The allowable bearing pressure is a net value; therefore, the weight of the foundation and the weight of backfill below the lowest grade adjacent to the structure may be neglected when computing dead loads.

Resistance to lateral loads may be calculated using an allowable passive equivalent fluid unit weight as described in Lateral Earth Pressures, Section 5.11. Both passive and frictional resistances may be assumed to act concurrently.

We estimate that total-post construction settlement of footings and RCBs designed and constructed in accordance with our recommendations will be on the order of 1 inch or less, with approximate differential settlement of on the order of ½ inch or less between adjacent similarly loaded isolated footings.



#### 5.10.1 Hydrostatic Uplift Pressures

All buried structures proposed to extend below the groundwater table are subjected to uplift pressures or buoyant forces. All structures extending below the groundwater table should be designed to resist these uplift pressures, especially the RCB if groundwater levels outside the culvert can exceed water depth in the culvert. Buoyant pressures can be found by multiplying the unit weight of water (62.4 pcf) by the depth below the groundwater table. For example if the bottom of the RCB was 10 feet below the design groundwater surface, a pressure of 624 psf would be applied across the bottom of the RCB.

#### 5.11 Retaining Structures and Lateral Earth Pressures

Lateral earth pressures will be imposed on all subterranean structures, including culverts and foundations. Table 7 and Table 8 present a list of lateral earth pressures with and without hydrostatic pressures, respectively, which we recommend for design and planning of structures. These values assume a level backfill. The values assume a minimum internal angle of friction of 32 degrees for imported or on-site granular, backfill material meeting the structural fill specification (section 5.3), and a unit weight of 120 pcf.

The lateral "at-rest" earth pressures should be used for design of the RCB. Lateral earth pressures acting against buried/retaining structures may be computed from the equivalent fluid densities presented below for the static case. The "active" condition may be used for walls that are able to deflect away from the backfill (i.e., unbraced walls). For walls that are not allowed to deflect, the "at-rest" condition should be used. The "passive" condition applies to walls or structures that move into the backfill. The uppermost 2 feet of the backfill should not be used for calculation of passive soil resistance unless it is protected by a permanent surface covering (pavement, slab, etc.). Maximum fluctuations in groundwater levels, should be considered in the design.



TABLE 7
PRELIMINARY LATERAL EARTH PRESSURES
WITH HYDROSTATIC PRESSURES

Earth Pressure	Equivalent Fluid Density
Active	80
At-rest	90
Passive	250
Friction Coefficient	0.40

TABLE 8
PRELIMINARY LATERAL EARTH PRESSURES
WITHOUT HYDROSTATIC PRESSURES

Earth Pressure	Equivalent Fluid Density
Active	35
At-rest	55
Passive	390
Friction Coefficient	0.40

The at-rest case is applicable for braced walls where rotational movement is confined to less than 0.001H. If greater movement is possible, the active case applies.

The lateral loads computed using the values in Tables 7 and 8 assume a level backfill and structural fill will extend laterally at least one-half of the wall height. If this condition does not apply, the design values may require revision. This backfill should be compacted to 90% of maximum dry density and within 2% of the optimum moisture content as determined by ASTM D1557. Over-compaction should be avoided, as the increased compactive effort will result in lateral pressures higher than those recommended above. Heavy compaction equipment or other loads should not be allowed in close proximity to the wall unless planned for in the structural design.

Recommended minimum factors of safety against sliding, overturning, and bearing failure are listed in Table 9, below.



TABLE 9
RECOMMENDED MINIMUM FACTORS OF SAFETY

Factor of safety against sliding	1.5
Factor of safety against overturning	To be determined by Structural Engineer
Factor of safety against bearing failure	3*

<sup>\*</sup> Factor of safety included in provided allowable bearing pressure.

If both passive and frictional resistances are assumed to act concurrently, we recommend a minimum safety factor of 2 be used for design against sliding.

#### 5.12 Special Areas

The following sections include specific discussions and recommendations for specific areas of the proposed alignment; adjacent to the existing NTD channel, the East Greg Street embankment, and the proposed Truckee River Levee crossing.

#### 5.12.1 Adjacent to the Existing NTD Channel

For approximately 1,000 feet from the confluence of the People's Drain to the Washoe County School District Property, the proposed NTD RCB crosses, is partially in, or is adjacent to the existing NTD channel. Special earthwork recommendations and settlement analyses are provided for this area.

Although no explorations were performed within the existing channel it is likely the channel bottom will consist of soft or loose clays, silts, and/or fine grained sands. These materials must be completely removed to expose at least firm or medium dense native material. For bidding purposes we recommend that two feet of the in-place material is removed and replaced with structural fill. However, the contract documents should provide flexibility in overexcavation of this area.

The proposed RCBs generally will be installed below existing grade and will generally weigh less than the excavated soil it replaces, therefore settlement will be minimal. An exception is in the vicinity of the existing NTD channel, where the existing ground



surface (in the ditch itself) is lower than the top of box culvert, and higher final stresses and settlement can potentially result. The greatest additional loading and potential for settlement will occur, not to construction of the RCB, but where the adjacent NTD ditch is backfilled adjacent to the new box culvert.

Settlement analysis was evaluated for the subsurface profile in the vicinity of boring B-6. The existing clay soils in this area under the existing NTD ditch are deepest in this area and have lower initial consolidation stresses due to less soil cover under the existing ditch. Settlement analysis was performed assuming overconsolidated clays based on laboratory testing in boring B-6. Incremental stresses were assumed to occur due to 11 feet of backfill from the bottom of the existing ditch to an expected 2 feet of fill over the top of the adjacent box culvert. These stresses were assumed to occur over a limited strip loading approximately 30 feet wide along the existing ditch footprint.

Total calculated settlement is in the range of 1½ to 2½ inches. A portion of the settlement will occur during backfill of the channel. We estimate that post-backfill settlements will be on the order of 1½ inches under the centerline of the channel, and any settlements will drop off rapidly under the new RCB, with little potential for significant differential settlement of the RCB.

It is estimated the majority of the settlement will occur within 1 year of backfill placement. We therefore recommend that construction of settlement-sensitive improvements over the drain ditch backfill within 1 year after the current construction should include settlement surveys for a 30-day waiting period prior to construction, with level surveys performed at the beginning and end of the waiting period, to verify that no remaining movement is occurring.

The settlement estimates are contingent on the assumption that the contractor's operations will not disturb the existing firm to soft clays at the bottom of the existing NTD channel.

#### 5.12.2 East Greg Street Embankment

Slope stability analyses were performed using SLIDE (Rocscience, 2008) to confirm global stability where the proposed culvert excavation will be parallel and adjacent to the existing East Greg Street embankment. The east side of the East Greg Street



embankment is built at 1.6H:1V and is 27 to 28 feet above existing grade at the north end of the parallel box culvert alignment. The invert of the box culvert in this area is 18 feet below existing grade, and the edge of the box culvert will be approximately 40 feet from the toe of the existing slope. Results of the slope stability analysis showed a factor of safety greater than 1.3 which is recommended for temporary construction conditions.

Kleinfelder understands that at the present time, the project team has selected to perform an open cut in the East Greg Street embankment to install the proposed RCB. Box culvert installation would be performed during a short duration (e.g. weekend) closure of East Greg Street, during which period the embankment would be excavated, box culvert would be constructed with precast concrete segments, and the embankment backfilled. For safety purposes, the excavation would have to be evaluated by the contractor. However, for preliminary design purposes, we expect that a temporary slope in the range of 1.5H:1V to 1.75H:1V would have an acceptable temporary slope factor of safety.

Other approaches could potentially include use of a vertical excavation with soil-nails or tied-back soldier piles, or jacking the new culverts into place under the existing embankment. These alternatives would only be necessary if it were not feasible to perform the necessary construction with a short-term closure. Soil-nail or soldier-pile shoring with tiebacks could potentially allow for detoured lanes of East Greg Street to remain open on one side of the embankment while the other side is excavated.

The soils are generally suitable for soil nails or tieback anchors, although some of these nails or anchors would potentially hit refusal in embankment or native granular soils. Longer nails or anchors would likely be required for the bottom of the excavation in the firm to stiff clays. Soldier piles would likely have to be installed in pre-augered holes backfilled with lean concrete, due to uncertainty of driving into fill and native soils with likely cobbles and boulders. The augered holes would have to be cased in the Tahoe Outwash. After completion of the first half of the culvert, a geotextile-wrapped-face mechanically-stabilized wall would generally be the most appropriate method to rebuild the embankment above the first half of the completed culvert. A jacked culvert installation may potentially be feasible given the subsurface conditions but is generally more costly. A specialty contractor and design would be required for the soil nail, tieback anchor, soldier pile, or jacked culvert installation option.



#### 5.12.3 Truckee River Levee and NTD Outfall

The proposed RCB will penetrate through native soils and fill below the existing Truckee River Levee just short of the outfall. We understand that the existing levee is owned by the City of Sparks and is neither United States Army Corps of Engineers (USACE) nor FEMA certified. Therefore special criteria for levee construction are not presented and we have not performed additional evaluation of levee stability or seepage. We propose the following backfill methods around the RCB so that the levee backfill will meet or be more stringent than the existing conditions.

We recommend that the levee prism, any excavation below the levee footprint, and backfill around the culvert in this excavation consist of low permeability backfill meeting USACE levee material requirements. Levee fill should have greater than 20 percent fines, 100 percent passing the 2-inch sieve, a plasticity index between 8 and 40, and a liquid limit of less than 45 percent (USACE 2004). These soils could include clays to clayey sands excavated from the existing levee or obtained from floodplain deposits along the RCB alignment. Levee soil shall be placed in 8 inch maximum loose lifts and compacted to a minimum density (ASTM D698) at a moisture content within 2 percent of optimum moisture content. Levee armoring should match existing materials, unless additional hydraulic design is required due to a protruding outfall.

The previous recommendations for mechanical subgrade stabilization under the box culvert should not be used for closer than 25 feet to the proposed levee centerline to avoid creating more permeable seepage paths under the levee. If subgrade stabilization is required in this area, a 2-foot-thick mat of sand-cement slurry, meeting the criteria for excavatable slurry backfill (Standard Specifications, 2007, Section 337.08) should be used in lieu of drain rock or rock fill.

It is Kleinfelder's understanding a future levee or floodwall alignment is proposed near the existing, uncertified levee. It is strongly recommended the design team notifies and discusses the proposed RCB with USACE.

The proposed outfall is shown as discharging slightly above the normal Truckee River water level (water elevation 4,375 feet) on a bench which is most likely composed of fine, poorly-graded sand or silty sand. Both due to the need to provide construction support and to reduce erosion potential, we recommend that a 2-foot thick mechanical



stabilizing fill be placed under headwall and erosion control improvements to replace the saturated sands. Adequate armoring and energy dissipation including rip-rap, cellular concrete mats, or cast-in-place concrete slabs should be used. A heavy non-woven filter/separation fabric such as Mirafi 180N or equal, is generally recommended for subsurface protection, separation, and filtration of underlying sandy soils, drainage layers, and armoring layers. Different geotextile products may be more appropriate for different applications.

#### 5.13 Site Drainage

Final surface grades should be designed so as to direct runoff water away from the proposed improvements and should not allow ponding. Reconstructed pavement areas should be sloped and drainage gradients maintained to match the existing conditions and carry all surface water off the site.

#### 5.14 Steel and Concrete Reactivity

Analytical testing of selected soil samples were performed to assess the potential for adverse reactivity with concrete and corrosivity with steel. Limited soil testing was performed on three samples, which may not be representative of all surface and subsurface soils on site. Kleinfelder is not a corrosion engineering consultant and all testing and results are for the Clients reference only. Sulfate, pH and resistivity results from WET Labs are included in Appendix B.

Resistivity testing indicates the subgrade soils have extremely varying resistivity ranging from 1,400 to 430,000 ohm-cm. The two lowest resistivity values (1,400 and 2,300 ohm-cm) were samples of fill soil. The source of the fill soils is not known. A corrosion engineer should review resistivity and pH testing results to determine if corrosion protection for metal elements should be incorporated into the design.

Soluble sulfate testing was performed to evaluate potential sulfate attack against Portland Cement Concrete. The soluble sulfate content of the samples tested ranged from 25 to 200 ppm. Therefore, based on these samples the potential for sulfate attack appears to be very low and conventional Type II cement may be used, according to data furnished by WET Laboratory and the requirements of Section 19, Table 19-A-4 of the 2003 *International Building Code*.

### KLEINFELDER Bright People. Right Solutions.

#### 6. ADDITIONAL SERVICES

#### 6.1 Project Bid Documents

It has been our experience during the bidding process, that contractors often contact us to discuss the geotechnical aspects of the project. Informal contacts between Kleinfelder and an individual contractor could result in incorrect or incomplete information being provided to the contractor. Therefore, we recommend a pre-bid meeting be held to answer any questions about the report prior to submittal of bids. If this is not possible, questions or clarifications regarding this report should be directed to the project Owner or his designated representative. After consultation with Kleinfelder, the project Owner (or his representative) should provide clarifications or additional information to all contractors bidding the job.

#### 6.2 <u>Construction Observation/Testing and Plan Review</u>

The recommendations made in this report are based on the assumption that an adequate program of tests and observations will be made during construction to verify compliance with these recommendations. These tests and observations should include, but not necessarily be limited to, the following:

- Part time observations and testing during site preparation and excavations.
- Review and comment on contractor submittals including shoring and dewatering.
- Observation and testing of construction materials.
- Full-time observations and testing during backfill.
- Consultation as may be required during construction.

We also recommend that project plans and specifications be reviewed by us to verify compatibility with our conclusions and recommendations. Additional information concerning the scope and cost of these services can be obtained from our office.



The review of plans and specifications and the field observation and testing by Kleinfelder are an integral part of the conclusions and recommendations made in this report. If we are not retained for these services, the Client agrees to assume Kleinfelder's responsibility for any potential claims that may arise during construction.



#### 7. LIMITATIONS

Preliminary recommendations contained in this report are based on our field explorations, laboratory tests, and our understanding of the proposed construction. The study was performed using a mutually agreed upon scope of work. It is our opinion that this study was a cost-effective method for evaluation of the subject site and evaluation of the potential geotechnical concerns.

The soils data used in the preparation of this report were obtained from borings made for this investigation. It is possible that variations in soils exist between the points explored. The nature and extent of soil variations may not be evident until construction occurs.

This report has been prepared for preliminary planning purposes for specific application to the North Truckee Drain project in accordance with the generally accepted standards of practice at the time the report was written. No warranty, express or implied, is made.

This report may be used only by the client and only for the purposes stated, within a reasonable time from its issuance, but in no event later than 3 years from the date of the report. Land or facility use, on and off-site conditions, regulations, or other factors may change over time, and additional work may be required with the passage of time. Based on the intended use of the report, Kleinfelder may require that additional work be performed and that an updated report be issued. Non-compliance with any of these requirements by the client or anyone else will release Kleinfelder from any liability resulting from the use of this report by any unauthorized party and client agrees to defend, indemnify, and hold harmless Kleinfelder from any claim or liability associated with such unauthorized use or non-compliance.



#### 8. REFERENCES

ASTM, 2008, Soil and Rock; Geosynthetics, Volumes 4.08, 4.09, and 4.13.

Bell, J.W., and Bonham, H.F., Vista Quadrangle Geologic Map, Nevada Bureau of Mines and Geology Reno Area, Scale 1:24,000, 1987.

Broadbent & Associates, 2008, Fourth Quarter, 2007, Ground-water Monitoring Report, Washoe County School District, Ghetto Transportation Facility, 1850 Kleppe Lane.

Federal Register, 1989, Construction Standards for Excavations, 29 CFR No. 209, Volume 54.

Gater, William C.B., and R. Watters, 1992, Geology of Reno and Truckee Meadows, Nevada, United States of America, Bulletin of the Association of Engineering Geologists, Vol. 29, No. 3.

Maurer, D.K., and Moffatt, R.L., Vista Quadrangle Groundwater Map, Nevada Bureau of Mines and Geology Reno Area, Scale 1:24,000, 1992.

HDR, Inc., 2009, North Truckee Drain Realignment, Alternatives Analysis Report. February 19, 2009.

Kleinfelder, 2007, Phase I Data Report, Tasks 1, 2, and 3, North Truckee Drain Realignment Project, Sparks Nevada, report to HDR dated June 21, 2007.

Louie, J.N., 2001, Faster, Better: Shear Wave Velocity to 100 Meters Depth from Refraction Microtremor Arrays Bulletin of the Seismological Society of America, Vol. 19, No. 2, pp 347-364.

Rocscience, Inc., 2003, Slide, v. 5.006, computer program, Toronto, Ontario.



Standard Specifications for Public Works Construction (SSPWC), 2006 (Washoe County, Sparks-Reno, Carson City, Yerington, Nevada).

Union Pacific Railroad, 2004, Guideline for Temporary Shoring, October 25, 2004.

U.S. Army Corps of Engineers (USACE), 2004, CESPK-ED-G Geotechnical Levee Practice SOP EDG-03, Sacramento District.

U.S. Army Corps of Engineers, 1970, Flood Plain Information, Truckee River, Reno-Sparks, Truckee Meadows, Nevada.

United States Geologic Survey, 2006, Quaternary Fault and Fold Database of the United States.



# **APPENDIX A**


**Previous Boring Logs** 


# **APPENDIX B**

**WET Lab Results** 

## **APPENDIX C**

Sections of Groundwater Report 2008, Broadbent & Associates, Inc.






Bright People. Right Solutions.


PROJECT NO. 102314,104


**DRAFTED BY:** 


K. Carter


**GEOTECHNICAL INVESTIGATION** SPARKS, NEVADA












































USCS.dwg

			TH	E UNIF	IED	SOIL	. CL	ASS	IFICATION SYSTEM
		į.	MAJOR DI	VISIONS		71		DUP BOLS	TYPICAL NAMES
				CLEAN GRA Less than 5%	VELS		GW		Well graded gravels, gravel - sand mixtures, little or no fines, Cu>4 & 1 <cc>3</cc>
Carter	ا م م	Mor	RAVELS than 50% of parse part is	finer than No. 200 Sieve.		*	GP	36.95 56.95 56.95	Poorly graded gravels or gravel - sand mixtures, little or no fines Cu<4 or 1>Cc<3
27 Aug 2009, 9:14am, KCarter	COARSE GRAINED SOIL More than 50% of the material is LARGER than the No. 200 sieve.	LAR	GER than the lo. 4 Sieve.	GRAVEL More than 12%	5		GM	60 00 00 00 00 00 00 00 00 00 00 00 00 0	Silty gravels, gravel - sand - silt mixtures
9, 9:14	RAINE of the r			finer than No. 200 Sieve.			GC		Clayey gravels, gravel - sand - clay mixtures
ug 200	RSE G lan 50% iR than 1		0444700	CLEAN SAN Less than 5% finer than	DS		sw		Well graded sands, gravelly sands, little or no or no fines, Cu>6 & 1 <cc>3</cc>
27 A	COA More th LARGE	Mon	SANDS e than 50% of parse part is	No. 200 Sieve.			SP		Poorty graded sands or gravelly sands, little or no fines Cu<6 or 1>Cc<3
PLOTTED:		_	IALLER than No. 4 Sieve.	SAND More than 12% finer than	,		SM		Silty sands, sand - silt mixtures
PLO				No. 200 Sieve.			sc		Clayey sands, sand - clay mixtures
					PI-Be	elow A-Line	ML		Inorganic slits, rock flour, or clayey silts of low plasticity
	SOIL THE EVE.		S AND CLAY Liquid limit ESS than 50	S	PI-Ab	ove A-Line	CL		Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays
	AINED 50% of 1 SMALLE 5. 200 si						OL		Organic silts & organic clays of low plasticity
	FINE GRAINED SOIL More than 50% of the material is SMALLER than the No. 200 sieve.				PI-Be	elow A-Line	МН		Inorganic silts, clayey silts, or silts of high plasticity
	A B B B		S AND CLAY Liquid limit EATER than 50	S	PI-At	oove A-Line	CH		Inorganic clays of high plasticity, fat clays
							ОН		Organic clays of medium to high plasticity, organic silts
USCS		HIGH	HLY ORGANI	C SOILS			PT	****	Peat & other highly organic soils
YOUT		BOUNDA	RY CLASSIFICA	TIONS: Solis posse	ssing cha			are designa	nated by combinations of group symbols.
إ≥	2					T	GRAVEL		SAND
L:\2009\Drafting\102314\Task 104\		ВО	ULDERS	COBBLE	S	Coarse	T	Fine	Coarse Medium Fine
14\Tas			12	eli .	3		3/4"		#4 #10 #40 #200 0.002 mm
1023				D	ESCR	IPTIVE TE	RMS U	SED W	/ITH SOILS
fing	T	CC		& APPARENT DE		S & GRAVEI	s		MOISTURE CONTENT
١٥	Strongest	ŧ	Hard		Very	Dense	-		Wettest Wet Very Moist
200 200			Very Stiff Stiff Medium S	41.65	Dens Med Loos	ium Dense			Moist Slightly Moist
	Weakest	+	Soft Very Soft			Loose			Driest   ↑ Dry
FILE:			10.700.1						- Water Level Observed After Exploration
S S	sources and is subject to	change withou	aut notice. Kleinfelder ma	complied from a variety of ikes no representations or	1				₹
	such information. This doc designed or intended as a	ument is not : construction de	intended for use as a la seign document. The use	iness, or rights to the use of and survey product nor is it or misuse of the information party using or misusing the	1				
					PF	ROJECT NO	. 102	314.104	KEY TO SOIL CLASSIFICATION PLATE
					DF	RAWN: AL	JGUST 2	27, 2009	AND TERMS
	( KI		VFF	LDEF		RAWN BY:	K. 1	MUJCIK	47
⋛	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \			ight Solutions		HECKED BY	r: D.	ADAMS	
S S		/	www.klein	_	FI	LE NAME:			PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT GEOTECHNICAL INVESTIGATION

GEOTECHNICAL INVESTIGATION SPARKS, NEVADA

# ATTACHED IMAGES: ATTACHED XREFS: RENO. NV

## **SYMBOLS**



Disturbed Bag or Bulk Sample



Standard Penetration Sample (1.4 inch I.D., 2.0 inch O.D.)



Modified California (Porter) Sample (2.0 inch I.D., 2.56 inch O.D.)



California Sample (2.5 inch I.D., 3 inch O.D.)



No Sample Recovery



Water Level Observed During Drilling



Water Level Observed After Drilling

### **COMMENTS**

NOTE: Blow count represents the number of blows required to drive a sampler through the last 12 inches of an 18 inch penetration. A standard 140 pound hammer with a 30.4 inch free fall is used to drive the sampler.

NOTE: The lines separating strata on the logs represent approximate boundaries only. The actual transition may be gradual. No warranty is provided as to the continuity of soil strata between borings.

The information included on this graphic representation has been compiled from a variety of sources and is subject to change without notice. Nathridiser makes no representations or warranties, express or implied, so a socuracy, completeness, themshees, or rights to the use of such information. This document is not intended for use as a land survey product nor is a designed or intended as a construction design document. The use or misuse of the information contained on this graphic representation is at the sole risk of the party using or misusing the




PROJECT NO.	102314.104
DRAWN: AUG	UST 27, 2009
DRAWN BY:	K. WUJCIK
CHECKED BY:	D. ADAMS
FILE NAME:	
USCS.dwg	

KEY TO BORING LOGS

PLATE

18

PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT GEOTECHNICAL INVESTIGATION SPARKS, NEVADA




COBBLES	GRA	VEL		SAND		SILT OR CLAY
COBBLES	coarse	fine	coarse	medium	fine	SILT OR CLAY

	Boring	Depth (ft.)		Description -	ASTM Classifi	cation		LL	PL	PI	Сс	Cu
•	B-01	15.0		LEA	N CLAY (CL)			48	27	21		
X	B-01	20.5	POOR	LY GRADED GRAV	/EL with SILT AN	D SAND (GP-GM)	)				2.82	143.50
	B-02	7.5	Y <sub>G</sub>	CLAYEY GR	AVEL with SAND	(GC)		31	18	13	***	
*	B-03 (MW)	1.0		CLAYEY GR	AVEL with SAND	(GC)		31	16	15		
0	B-03 (MW)	10.0		CLAYEY GR	AVEL with SAND	(GC)		32	14	18		
	Boring	Depth (ft.)	D100	D60	D30	D10	% Gravel	9	6 Sand	% Si	lt s	% Clay
•	B-01	15.0	0.25				0.0		3.0		97.0	
X	B-01	20.5	50	15.707	2.202	0.109	62.0		29.2		8.8	
▲	B-02	7.5	50	8.539	0.601		51.0		33.0	-	16.0	
*	B-03 (MW)	1.0	37.5	6.268	0.344		46.0	.4.	36.0		18.0	
0	B-03 (MW)	10.0	50	8.27	0.85	90	52.0		31.0		17.0	



PLATE

19



### **GRAIN SIZE IN MILLIMETERS**


į	CORRI ES	GRA	VEL		SAND		
	COBBLES	coarse	fine	coarse	medium	fine	SILT OR CLAY

	Boring	Depth (ft.)		Description	- ASTM Classific	cation		LL	PL	PI	Сс	Cu
•	B-04	0.5		GRAVELLY FA	AT CLAY with SAN	ID (CH)		60	27	33		
	B-04	10.0		ELASTIC SILT (MH)					31	28		
▲	B-04	15.5		POORLY GRADED SAND (SP)							1.10	2.96
*	B-05	20.0		SANDY LEAN	CLAY with GRAVI	EL (CL)		47	21	26		
0	B-06	5.0			69 28		41					
	Boring	Depth (ft.)	D100	D60	D30	D10	% Grave	9/	6 Sand	% Sil	t 9	% Clay
•	B-04	0.5	50	0.278			31.0		15.0		54.0	
	B-04	10.0	12.5				1.0		12.0	,	87.0	
▲	B-04	15.5	2	0.511	0.311	0.172	0.0		96.3		3.7	
*	B-05	20.0	37.5	0.561			21.0		29.0		<b>5Q.0</b>	
0	B-06	5.0	2				0.0		5.0		95.0	



PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT **GEOTECHNICAL INVESTIGATION** SPARKS, NEVADA

**PLATE** 



### **GRAIN SIZE IN MILLIMETERS**

COPPLES	GRA		Ε.	SAND		CILT OD CLAY
COBBLES	coarse	fine	coarse	medium	fine	SILT OR CLAY


	Boring	Depth (ft.)		Description -	ASTM Classific	cation		LL	PL	PI	Сс	Cu
•	B-06	22.0		SANDY	LEAN CLAY (CL)			42	22	20		
×	B-07 (MW)	16.5		FA	T CLAY (CH)			78	30	48		
lack	B-07 (MW)	24.5		LEA	N CLAY (CL)							
*	B-07 (MW)	25.0	POORL	Y GRADED GRAV	EL WTH SILT AN	D SAND (GP-GM)					1.72	92.95
0	B-07 (MW)	29.5		CLAY	EY SAND (SC)							
	Boring	Depth (ft.)	D100	D60	D30	D10	% Gravel	1	% Sand	% Sil	t 9	% Clay
•	B-06	22.0	12.5				2.0		29.0		69.0	
	B-07 (MW)	16.5	0.425			*	0.0		3.0		97.0	
▲	B-07 (MW)	24.5	2				0.0		6.0		94.0	
*	B-07 (MW)	25.0	37.5	10.175	1.386	0.109	56.0		35.2		8.8	
0	B-07 (MW)	29.5	4.75	0.266			0.0		57.0		43.0	



PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT **GEOTECHNICAL INVESTIGATION** SPARKS, NEVADA

21

**PLATE** 



COBBLES	GRA	VEL		SAND		SILT OR CLAY
COBBLES	coarse	fine	coarse	medium	fine	SILT OR CLAY


	Boring	Depth (ft.)		Description	- ASTM Classific	ation		LL	PL	PI	Сс	Cu
•	B-08	15.5		SANDY	LEAN CLAY (CL)			35	19	16		
×	B-08	20.5		SILTY SAN	D with GRAVEL (	SM)						
	B-09	21.0	CLAYEY SAND with GRAVEL (SC)					37	18	19		
*	B-10	10.0		CLAYEY GR	AVEL with SAND	(GC)		32	19	13		
0	B-10	27.5	LEAN CLAY with SAND (CL)						20	24		
	Boring	Depth (ft.)	D100	D60	D30	D10	% Gravel	%	Sand	% Sil	t '	% Clay
•	B-08	15.5	4.75			11111111	0.0		37.0		63.0	
×	B-08	20.5	50	2.668	0.27		36.0		45.0		19.0	
lack	B-09	21.0	25	1.131			24.0		34.0		42.0	
*	B-10	10.0	37.5	5.985	0.326		44.0		36.0		20.0	
0	B-10	27.5	12.5				2.0		24.0		74.0	



GRAIN SIZE ANALYSES

PLATE

22



CORRIES	GRA	VEL		SAND			
CODDLES	coarse	fine	coarse	medium	fine	SILT OR CLAY	


	Boring	Depth (ft.)		Description -	- ASTM Classifi	cation		L	PL	PI	Сс	Cu
•	B-11 (MW)	10.5		POORLY GRADE	D SAND with SIL	T (SP-SM)	ı	IP	NP	NP	1.52	3.01
X	B-12	5.0		CLAYEY SA	ND with GRAVEL	(SC)	:	28	14	14		
▲	B-12	17.5	POOR	POORLY GRADED GRAVEL with SILT AND SAND (GP-GM)						Ш,	1.58	46.10
*	B-13	10.0		CLAYEY GR	AVEL with SAND	(GC)	;	31	17	14		
0	B-13	25.0		LEAN CL	AY with SAND (C	L)	;	32	22	10		
	Boring	Depth (ft.)	D100	D60	D30	D10	% Gravel	%	Sand	% S	ilt	% Clay
•	B-11 (MW)	10.5	0.85	0.226	0.161	0.075	0.0		90.0		10.0	
X	B-12	5.0	25	0.518			19.0		45.0		36.0	
lack	B-12	17.5	37.5	9.72	1.797	0.211	56.0		37.7		6.3	
*	B-13	10.0	37.5	4.75	0.25		40.0		36.0		24.0	
0	B-13	25.0	19				2.0		20.0		78.0	



**GRAIN SIZE ANALYSES** 

PLATE

**23** 




COBBLES	GRA	VEL		SAND		SHITOPCIAV
	coarse	fine	coarse	medium	fine	SILI OR CLAY

	Boring	Depth (ft.)		Description -	- ASTM Classific	ation		LL PL	PI	Сс	Cu
•	B-14	7.5		FA	T CLAY (CH)			64 23	41		
M	B-14	12.5		LEAN CL	AY with SAND (CL	.)		49 23	26		
▲	B-14	16.0		SIL	TY SAND (SM)						
				T				,			
	Boring	Depth (ft.)	D100	D60	D30	D10	% Gravel	% Sand	% Silf	9	% Clay
•	B-14	7.5	4.75				0.0	12.0		88.0	
×	B-14	12.5	4.75				0.0	17.0		83.0	
▲	B-14	16.0	0.85	0.119			0.0	60.0		40.0	
٦				7.5							



24

**PLATE** 



	Specimen Identification	LL	PL	PI	Fines	Classification
•	B-01 15.0	48	27	21	97	LEAN CLAY (CL)
X	B-02 7.5	31	18	13	16	CLAYEY GRAVEL with SAND (GC)
<b>A</b>	B-03 (MW) 1.0	31	16	15	18	CLAYEY GRAVEL with SAND (GC)
*	B-03 (MW) 10.0	32	14	18	17	CLAYEY GRAVEL with SAND (GC)
0	B-04 0.5	60	27	33	54	GRAVELLY FAT CLAY with SAND (CH)
٥	B-04 10.0	59	31	28	87	ELASTIC SILT (MH)
0	B-05 20.0	47	21	26	50	SANDY LEAN CLAY with GRAVEL (CL)
Δ	B-06 5.0	69	28	41	95	FAT CLAY (CH)
8	B-06 22.0	42	22	20	69	SANDY LEAN CLAY (CL)
0	B-07 (MW) 16.5	78	30	48	97	FAT CLAY (CH)
_		1				L




PLATE

**25** 

DRAFTED BY: K. CARTER PROJECT NUMBER: 102314.104

PLASTICITY INDEX



	Specimen Identification	LL	PL	PI	Fines	Classification
•	B-08 15.5	35	19	16	63	SANDY LEAN CLAY (CL)
×	B-09 21.0	37	18	19	42	CLAYEY SAND with GRAVEL (SC)
<u> </u>	B-10 10.0	32	19	13	20	CLAYEY GRAVEL with SAND (GC)
*	B-10 27.5	44	20	24	74	LEAN CLAY with SAND (CL)
0	B-11 (MW) 10.5	NP	NP	NP	10	POORLY GRADED SAND with SILT (SP-SM)
O	B-12 5.0	28	14	14	36	CLAYEY SAND with GRAVEL (SC)
0	B-13 10.0	31	17	14	24	CLAYEY GRAVEL with SAND (GC)
Δ	B-13 25.0	32	22	10	78	LEAN CLAY with SAND (CL)
8	B-14 7.5	64	23	41	88	FAT CLAY (CH)
Φ	B-14 12.5	49	23	26	83	LEAN CLAY with SAND (CL)




PLATE

26

DRAFTED BY: K. CARTER PROJECT NUMBER: 102314.104

**PLASTICITY INDEX** 



S	Specimen Identification		ntification Classification			С	ф
•	B-01	13.5	LEAN CLAY (CL)	82	37	408	28
×	B-03 (MW)	8.5	FILL: CLAYEY GRAVEL WITH SAND (GC)	113	9	424	36
▲	B-06	15.0	SANDY LEAN CLAY (CL)	80	37	955	17
*	B-11 (MW)	10.0	POORLY GRADED SAND with SILT (SP-SM)	91	25	625	36
0	B-14	11.0	FAT CLAY (CH)	86	32	691	27
٥	B-15	11.0	POORLY GRADED SAND (SP)	80	27	220	36




27

DRAFTED BY: K. CARTER

**PROJECT NUMBER: 102314.104** 

**DIRECT SHEAR TEST** 

PLATE



STRESS, psf

Specimen Identification		tion	Classification			MC%
•	B-06	20.5	SANDY LEAN CLAY (CL)		96	28
_			The Residence of the Control of the			
$\dashv$						ļ
+						




PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT GEOTECHNICAL INVESTIGATION SPARKS, NEVADA

**28** 

**PLATE** 

CONSOLIDATION

DRAFTED BY: K. CARTER PROJECT NUMBER: 102314.104



STRESS, psf

Specimen Identification		entification Classification		MC%
•	B-07 (MW) 20.0	FAT CLAY (CH)	78	40
1	*3			
-1				




PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT GEOTECHNICAL INVESTIGATION SPARKS, NEVADA

CONSOLIDATION

PLATE

29



STRESS, psf

Specimen Identification		ntification	Classification	$\gamma_{\rm d}$	MC%	
•	B-13 30.5		LEAN CLAY WITH SAND (CL)	112	15	
1					1	
+						
					-	




PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT **GEOTECHNICAL INVESTIGATION** SPARKS, NEVADA

CONSOLIDATION

PLATE 30

**PROJECT NUMBER: 102314.104** 

DRAFTED BY: K. CARTER



The information included on this graphic representation has been compiled from a variety of sources and is subject to change without notice. Kleinfelder makes no representations or warranties, expresse or implied, so to accuracy, completaness, trainess, or rights to the use of such information. This document is not intended for use as a land survey product nor is it designed or inferned as a construction design document. The use or misuse of the information contained on this graphic representation is at the sole risk of the party using or misuseing the information.

REFERENCE: GROUNDWATER DATA OBSERVED FROM BROADBENT & ASSOCIATES, INC. GROUNDWATER LEVELS REPORT (2008)



	PROJECT NO.	102314.104
	DRAWN:	SEPT. 3, 2009
,	DRAWN BY:	K. CARTER
	CHECKED BY:	J. PEASE
	FILE NAME:	

LONG TERM GROUNDWATER ELEVATIONS IN PROJECT VICINITY PROPOSED NORTH TRUCKEE DRAIN REALIGNMENT


GEOTECHNICAL INVESTIGATION SPARKS, NEVADA


31

PLATE

# **APPENDIX A**

**Previous Boring Logs** 





# **APPENDIX B**

**WET Lab Results** 

### Western Environmental Testing Laboratory **Analytical Report**

Kleinfelder, Inc.

Date Printed:

8/18/2009

4835 Longley Lane

OrderID:

0908113

Reno, NV 89502

Attn: Don Adams

Phone: (775) 689-7800 Fax: (775) 689-7810

PO\Project:

North Truckee Drain Reanlignment/102314.103

Customer Sample ID:

B-10 Bulk 10'-15'

Collect Date/Time: 8/12/2009

WETLAB Sample ID:

0908113-001

Receive Date: 8/12/2009 12:25

Parameter	Method	Results	Units	Reporting Limit	Date Analyzed
Sulfate	EPA 300.0	200	mg/kg	15	8/14/2009
Paste pH	SW846 9045B	8.05	pH Units		8/17/2009
Resistivity	SM 2510B	2300	ohms.cm	1.0	8/17/2009

Customer Sample ID:

B-8 Baggie 12.5-14

Collect Date/Time: 8/12/2009

WETLAB Sample ID:

0908113-002

Receive Date: 8/12/2009 12:25

Parameter	Method	Results	Units	Reporting Limit	Date Analyzed
Sulfate	EPA 300.0	45	mg/kg	15	8/14/2009
Paste pH	SW846 9045B	7.63	pH Units		8/17/2009
Resistivity	SM 2510B	6200	ohms.cm	1.0	8/17/2009

Customer Sample ID:

B-7 Baggie 0-1.5

Collect Date/Time: 8/12/2009

WETLAB Sample ID:

0908113-003

Receive Date: 8/12/2009 12:25

Parameter	Method	Results	Units	Reporting Limit	Date Analyzed
Sulfate	EPA 300.0	91	mg/kg	15	8/14/2009
Paste pH	SW846 9045B	7.56	pH Units		8/17/2009
Resistivity	SM 2510B	1400	ohms.cm	1.0	8/17/2009

## Western Environmental Testing Laboratory **Analytical Report**

Kleinfelder, Inc. 4835 Longley Lane Date Printed: OrderID:

4/20/2009

Reno, NV 89502

0904115

Attn: Don Adams

Phone: (775) 689-7800 Fax: (775) 689-7810

PO\Project:

North Truckee Drain / 9474

Customer Sample ID:

B-1 bulk 12-18

Collect Date/Time: 4/10/2009

WETLAB Sample ID:

0904115-001

Receive Date: 4/13/2009 17:10

Parameter	Method	Results	Units	Reporting Limit	Date Analyzed	
Sulfate	EPA 300.0	160	mg/kg	15	4/15/2009	
Paste pH	SW846 9045B	7.30	pH Units		4/15/2009	
Resistivity	SM 2510B	5400	ohms.cm	1.0	4/15/2009	

Customer Sample ID:

B-3 bulk 10-12

WETLAB Sample ID: 0904115-002 Collect Date/Time: 4/10/2009

Receive Date: 4/13/2009 17:10

Parameter	Method	Results	Units	Reporting Limit	Date Analyzed
Sulfate	EPA 300.0	68	mg/kg	15	4/15/2009
Paste pH	SW846 9045B	7.73	pH Units		4/15/2009
Resistivity	SM 2510B	69000	ohms.cm	1.0	4/15/2009

Customer Sample ID:

B-11 bulk 5-7.5

WETLAB Sample ID: 0904115-003 Collect Date/Time: 4/10/2009

Receive Date: 4/13/2009 17:10

P	Method	Results	Units	Reporting Limit	Date Analyzed
Parameter	Metada	Resuits	Onits	Zitiitt	7 Kilaly Zee
Sulfate	EPA 300.0	25	mg/kg	15	4/15/2009
Paste pH	SW846 9045B	7.59	pH Units		4/15/2009
Resistivity	SM 2510B	430000	ohms.cm	1.0	4/15/2009

# **APPENDIX C**

Sections of Groundwater Report 2008, Broadbent & Associates, Inc.

FOURTH QUARTER, 2007
GROUND-WATER MONITORING REPORT
WASHOE COUNTY SCHOOL DISTRICT
GETTO TRANSPORTATION FACILITY
1850 KLEPPE LANE

RECEIVED

FEB 0 4 2008

WASHOE COUNTY 3CHOOL DISTRICT REGULATED SYSTEMS & ASSESSMENT Per John Nolan:

All Monstrong Wells are growted/removed.

Prepared for


Mr. John Nolan Washoe County School District 7495 South Virginia Street Reno, Nevada 89520

Prepared by

BROADBENT & ASSOCIATES, INC.
2000 Kirman Avenue
Reno, NV 89502
(775) 322-7969
www.broadbentinc.com

February, 2008

Project No. 98-02-573



Page 1 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

				Spa	Sparks, Nevada	œ						
Well		MPE	DTW	Water Level	TPHg	TPH-E	Benzene	Toluene	Xylenes	E-Benzene	MTBE	
Number	Date	€	ŧ	( <del>t)</del> )	(mg/l)	(mg/l)	(ug/l)	(ng/l)	(ug/l)	(l/gn)	(l/gu)	
MW-1	1/21/1999	99.57	9.39	90.18	2	i	2	Q.	Š	Ę	102	
	4/29/1999		8.3	91.27	2	i	2	2	2	2 5	701	
	8/3/1999		8.28	91.29	£	i	2	2	2	2	26.8	
	2/15/2000		10.15	89.42	I	Q N	Q.	2	2	2	12.1	
	6/5/2000		9.62	89.95	R	i	Q N	2	2	Q.	7.5	
	9/5/2000		9.81	89.76	Ð	1	R	2	2	<del>Q</del>	2	
	11/14/2000		9.95	89.62	2	i	2.2	3.7	3.9	æ	44.8	
	2/20/2001		^20.23	79.34	<0.5	I	<b>6.7</b>	2.0	2.0	2.0	9.8	
	6/13/2001		9.74	89.83	<0.5	I	0.2	7.0	<b>2</b> .0	2.0	94.6	
	8/28/2001		9.62	89.95	0.67	I	2.0	2.0	2.0	<b>42.0</b>	663.5	
	11/16/2001		99.6	89.91	1.13	I	2.0	2.0	2.0	<2.0	1129.8	
	3/6/2002		NA	NA	<0.05	I	2.0	0.7	2.0	<b>2.0</b>	<2.0	
	6/6/2002	4389.92	8.64	4381.28	0.58	1	0.2	0.7	<b>4</b> 7.0	<b>2.0</b>	572	
	9/16/2002		9.39	4380.53	0.29	I	2.0	<b>2</b> .0	2.0	<2.0	293	
	12/30/2002		9.85	4380.07	<0.05	ł	<1.0	<1.0	<1.0	<1.0	2.1	
	3/13/2003		10.16	4379.76	<0.05	I	2.0	7.0	2.0	<2.0	<2.0	
	4/22/2003		9.98	4379.94	Z	I	¥Z.	¥Ζ	Σ	MN	N	
	5/28/2003		9.90	4380.02	Σ	i	MN	MN	MN	MN	MN .	
	6/20/2003		68.6	4380.03	<0.5	I	<1.0	<1.0	<1.0	⊲.0	12	
	7/31/2003		10.11	4379.81	W	i	MZ	MN	MN	MN	MX	
	9/30/2003		10.29	4379.63	<0.05	i	<0.5	<0.5	6.0	<0.5	0.7	
	11/5/2003		10.37	4379.55	MN	I	ΣX	MN	ΜN	NM	MN	
	12/18/2003		10.54	4379.38	<0.02	i	<1.0	<1.0	0.7	<1.0	2.3	
	3/22/2004		10.28	4379.64	<0.02	l	<1.0	<1.0	<b>6.7</b>	<1.0	<1.0	
	6/3/2004		10.25	4379.67	<0.02	I	<1.0	<1.0	77.0	<1.0	1.7	
	9/30/2004		10.61	4379.31	<0.01	I	<1.0	<1.0	<1.0	<1.0	1.5	
	12/29/2004		10.62	4379.30	<0.01	I	<1.0	√1.0	2.0	<1.0	<1.0	25
	3/23/2005		9.41	4380.51	<0.02	i	<1.0	<1.0	0.7	<1.0	<1.0	
•	4/14/2005		9.58	4380.34	1	I	ł	I	1	i	i	
	5/27/2005		8.70	4381.22	-	j	1	ł	I	}	1	
	6/29/2005		8.56	4381.36	<0.50	;	<1.0 <1.0	<1.0	<1.0	<1.0	1.1	
	7/25/2005		8.82	4381.10	1	I	į	1	1	1	I	
	8/30/2005		9.16	4380.76	i	I	ı	į	1	i	I	

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada.

	MTBE	(ng/l)	2	 	ı	i	2.0	1		8	-	ı	<1.0	<1.0	1.0	<1.0	1.0	. 48			2,600	5,946	944	604	1,668	838	20.0	0.10	400	83.4	0.50	98	. 24	21	38	200	N N	M
				•••	•	•	•		•		29	•	٧	٧		٧	٧						<u>.</u>	7.	1	, 2	. 4	79	1,	12	99	2		7	4	4	Z	Z
	E-Benzene	(ug/l)	7	2.7/	i	I	<1.0	ı	ı	<1.0	1	,	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		S	S	24	2	2	2	2	2.0	2.0	2.0	2.0	2.0	2.0	3.0	<1.0	<2.0	Z	Z
	Xylenes	(ng/l)	7	2.17	i	I	<1.0	I	i	<1.0	i	i	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2	£	32	£	2	2	2	<2.0	<b>7.0</b>	2.0	<b>2</b> .0	<2.0	2.0	18.2	<1.0	2.0	XX	Z
	Toluene	(ug/l)	V 10	2.7	I	I	<1.0	i	i	<1.0	I	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2	2	24	2	Q	2	2	0.2	7.0	<b>7</b> .0	<b>6.</b> 2	2.0	2.0	12.9	<1.0	2.0	MN	2
	Benzene	(ug/l)	7	2.7	I	l	<1.0	I	I	<1.0	I	I	<1.0 <1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2	2	2	2	2	2	2	2.0	2.0	<b>2</b> .0	<b>6.7</b>	<b>2</b> .0	2.0	2.0	<1.0	2.0	ΣX	2
æ	TPH-E	(mg/l)			i	I	I	I	I	I	I	ı	ı	I	I	i	I	i	l		I	l	1	2	1	i	ŀ	i	i	1	i	I	ł	I	ļ	į	i	ł
parks, Nevada	TPHg	(mg/l)	05.0>		I	ļ	<0.50	I	i	<0.50	I	i	i	i	I	<0.50	I	<0.50	<0.50		۰ ه	9	7.1	I	1.7	2.84	4.5	0.8	1.4	1.29	0.61	<0.05	0.43	0.75	0.44	0.45	NM	Z
Spa	Water Level	(ft)	4380.16	420022	4360.33	45/9.89	4380.04	4382.76	4382.64	4382.06	4382.11	4382.80	4382.53	4381.18	4379.88	4379.02	4379.42	4379.61	4384.88	60.00	69.33	90.06	90.25	89.12	89.37	89.35	89.17	78.59	89.53	89.82	89.56	NA	4381.57	4380.81	4379.97	4379.75	4380.09	4380.30
	DTW	<b>(£</b> )	9.76	0 4 0	٧٥.٢	10.03	88.6	7.16	7.28	7.86	7.81	7.12	7.39	8.74	10.04	10.90	10.50	10.31	5.04	8	7.7	8.66	9.07	10.20	9.95	9.97	10.15	^20.73	9.79	9.50	9.76	NA	8.64	9.40	10.24	10.46	10.12	16.6
	MPE	Œ																		25.00	72.24												4390.21					
		Date	9/29/2005	10/21/2005	11/20/2002	11/30/2005	12/29/2005	1/24/2006	2/1/2006	3/1/2006	4/27/2006	5/31/2006	6/23/2006	9/8/2006	12/28/2006	3/26/2007	6/1/2007	9/7/2007	1/4/2008	1/21/1000	1,001,000	4/29/1999	8/3/1999	2/15/2000	6/5/2000	9/5/2000	11/14/2000	2/20/2001	6/13/2001	8/28/2001	11/16/2001	3/6/2002	6/6/2002	9/16/2002	12/30/2002	3/13/2003	4/22/2003	5/28/2003
	Well	Number	MW-1	1 10	COIII.															C IND	7- M I/I													•				

Page 2 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

11-722				d <sub>S</sub>	Sparks, Nevada	æ						
Well	1	MFE	M I C	Water Level	TPHB	TPH-E	Benzene	Toluene	Xylenes	E-Benzene	MTBE	
Numper	Date	€	€	( <del>U</del> )	(mg/l)	(mg/l)	(ug/l)	(l/gn)	(ug/l)	(l/gn)	(l/gn)	
	9							-11				
7-MW	7/31/2003		10.42	4379.79	ΣZ	I	ΣZ	ΣZ	Z	Z	ZZ	
Cont.	9/30/2003		10.41	4379.80	0.42	ł	<0.5	<0.5	<0.5	\$ 0 \$	422	
	11/5/2003		10.63	4379.58	MZ	i	MN	Z	Z	N N	NIV.	
	12/18/2003		10.68	4379.53	90.0	i	<1.0	V   V	0	7	IAIAI	
	3/22/2004		10.33	4379.88	0.037	ı	<1.0	0.12	0	0 7	37.3	
	6/3/2004		10.56	4379.65	0.20	I	0	0 V	9 6	7.7	37.7	
	9/30/2004		10.98	4379.23	0.192	I	0 7	? <del>.</del> .	7 7	? ?	8 5	
	12/29/2004		10.99	4379.22	0.190	I	0 V	? \ \	? ?	2.7	192	
	3/23/2005		9.86	4380,35	0.071	I	0 7 ∇	2.7	3 6	2.5	188	
	4/14/2005		9.94	4380.27		ı	; ;	2.17	?	2.1/	۸۵.8	
	5/27/2005		8.76	4381 45		ı	ł	i	ı	I	I	
	5000/00/9		07.0	4201.43	1	I	1	:	1	I	ł	
	2007/2007		0.07	4381.34	<0.50	I	0.1>	<b>0.</b> Γ	√ 7.0	~1 <u>.0</u>	140	
	2007/27/		9.23	4380.98	l	I	1	I	i	i	ł	
	8/30/2005		9.31	4380.90	1	ļ	1	***	ı	i	I	
	9/29/2005		9.42	4380.79	<0.50	l	<b>0'1</b> >	0.1>	<1,0	<1.0 <1.0	. 001	*
	10/31/2005		9.75	4380.46	I	1	I	i	ł	1	]	
	11/30/2005		10.27	4379.94	ı	ı	ı	I	ł	ı		
	12/29/2005		9.91	4380.30	<0.50	ı	<b>~1.0</b>	<1.0	<1.0	<1.0	. '42	
	1/24/2006		7.53	4382.68	ł	ı	i	i	I	1	!	
	2/1/2006		7.68	4382.53	i	I	I	ı	i	ł		
	3/1/2006		8.18	4382.03	<0.50		<1.0	<1.0	V-1.0	0	140	
	4/27/2006		7.94	4382.27	I	I	I	1		2 1	2	
	5/31/2006		7.24	4382.97	i	I	I	I	I			
	6/23/2006		7.53	4382.68	i	ł	<1.0	<1.0	0.15	012	130	
	9/8/2006		8.94	4381.27	i	ı	<1.0	<1.0	√1.0 	?;   	× ×	
	12/28/2006		10.37	4379.84	ł	I	<1.0	<1.0	0.1>	2.  -  -	87	
	3/26/2007		11.19	4379.02	<0.50	I	<1.0	<1.0	<1.0	<1.0	150	
	6/1/2007		10.59	4379.62	ă.	I	<1.0	<1.0	<1.0	0 1	45	
	9/7/2007		10.35	4379.86	<0.50	I	<1.0	<1.0	V \	<1.0	45	
	1/4/2008		1.67	4382.54	<0.50	i	<1.0	<1.0	<1.0	0.1>	5.9	
MW-3	1/21/1999	72.66	9.75	90.02	25		870	340	1.978	1.360	23 100	
	4/29/1999		8.49	91.28	14.7	1	268	340	144	728	12 464	
	8/3/1999		8.95	90.82	15.2	I	120	100	280	3 5	14,504	
	2/15/2000		10.60	89.17	ı	2	0.6	£	2.5	22.5	8 280	
	6/5/2000		9.91	89.86	7.1	į	104.0	2	132.0	E	0,700	
							,		>	116	0,000	

Page 3 of 28

Page 4 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

0.000000000000000000000000000000000000	0.000000000000000000000000000000000000	0.000000000000000000000000000000000000	0.000000000000000000000000000000000000	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00	2.20 2.20 2.20 2.20 2.20 2.20 2.20 2.20	2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00	2.00 2.00 2.00 2.00 2.00 3.00 3.00 3.00	2.70 2.70 2.70 3.80 8.86 8.86 8.86 8.86 8.66 8.70 1.44 1.44 1.60 1.60 1.60 1.60 1.60 1.60 1.60 1.60
N N N N N N N N N N N N N N N N N N N	N N N N N N N N N N N N N N N N N N N	N N N N N N N N N N N N N N N N N N N	N N N N N N N N N N N N N N N N N N N	N N N N N N N N N N N N N N N N N N N
M	M	M	M	M
4.4 NM	4.4 NM	4.4 NM	A.0	4.4 NM
NM	MM	MM	MM	MM
MM MM	MM MM	MM MM	MM MM	MM MM
41.0 41.0	13   13   13   13   13   13   13   13	41.0 41.0	\$\\\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\	4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0
0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.1.0 0.0 0	0.1.0 0.0 0	0.1.0 0.0 0	0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10
0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	11.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0
0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.10 0.10 0.10 0.10 0.10 0.10 0.10 0.10	0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0
0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	0.00	0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0
61.0 61.0 61.0 61.0 61.0	0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.	0;0 0;0 1,0 1,0 1,0 1,0 1,0 1,0 1,0	\$\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	\$\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
<ul><li>0.10</li><li>0.10</li><li>1.0</li><li>1.0</li><li>1.0</li></ul>	<ul><li>41.0</li><li>41.0</li><li>41.0</li><li>41.0</li><li>41.0</li><li>41.0</li></ul>	0.1.0 0.1.0 1.1.0 1.1.0 1.1.0	0.1.0 0.1.0 1.1.0 1.1.0 1.1.0 1.1.0	0.10
<  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  <  < <  <  <  <  <  < <  <  <  <  <  < <  <  <  <  <  < <  <  <  <  <  < <  <  <  <  <  < <  <  < < < < < < < < < <	1 1.0 1	1 1 0 1 1	1 1 0 1 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0	1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
<1.0 <1.0	< 4.0 < 1.0 < 1.0	<1.0 <1.0 <1.0 <1.0 <1.0	41.0 41.0 41.0 41.0 41.0 41.0 41.0	4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0
<1.0 <1.0	<1.0 <1.0	<1.0 <1.0	<1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0	<1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0
	1		41.0 <1.0	1 1.0

Summary of Ground-Water Monitoring Data WCSD-Getto Transportation Facility,

				Spa	Sparks, Nevada	æ					
Well		MPE	DTW	Water Level	TPHg	TPH-E	Benzene	Toluene	Xylenes	E-Benzene	MTBE
Number	Date	€	(¥)	( <del>tj</del> )	(mg/l)	(mg/l)	(l/gn)		(ng/l)	(l/gu)	([/dn)
MW-3	3/1/2006		7.83	4382.28	<0.50	I	<1.0	V. 1.0	<1.0	0.12	48
Cont.	4/27/2006		7.36	4382.75	i	ł	I	I	ı	1	2
	5/31/2006		6.63	4383.48	1	I	I	I	I	I	I
	6/23/2006		6.78	4383.33	I	I	<1.0	<1.0	Q 1 V	, V	1.
	9/8/2006		8.52	4381.59	ļ	I	<1.0	<1.0	V 1.0	0.0	12.
	12/28/2006		10.31	4379.80	I	I	<1.0	V 10	Q 1 >	2 7	3 5
	3/26/2007		11.17	4378.94	<0.50	i	<1.0	0.12	0.1	? V	35
	6/1/2007		10.50	4379.61	i	ł	√1.0 √1.0	Q.[>	V 1.0	7	35
	9/7/2007		10.22	4379.89	<0.50	I	1.2	0.1>	<1.0	2.0	5.5
	1/4/2008		3.54	4386.57	<0.50	ŀ	4.0	<1.0	4.0	1.2	1.3
MW-4	4/29/1999	99.95	8.34	91.61	25		80	24	964	252	752
	8/3/1999		8.09	91.86	2.4	I	78	20	700	160	1.260
	2/15/2000		9.27	89.06	į	£	5.3	2	£	<u>S</u>	87.4
	6/5/2000		9.32	90.63	£	I	13.1	8	S	11.9	227.9
	9/5/2000		8.92	91.03	2	i	2	2	S	R	81.4
	11/14/2000		9.10	90.85	0.8	I	£	2	8.9	£	750.0
	2/20/2001		^19.94	80.81	<0.5	ı	0.7	7.0	7.0	<b>42.0</b>	341.0
	6/13/2001		8.40	91.55	<0.5	i	6.0	<b>7</b> .0	2.0	2.0	0.09
	8/28/2001		8.16	91.79	<0.5	I	7.0	7.0	<2.0	25.0	254.7
	11/16/2001		8.40	91.55	<0.5	i	2.0	<b>7</b> 70	0.7	2.0	51.0
	3/6/2002		N A	NA	0.15	I	16	0.7	2.0	46	170
	6/6/2002	4390.19	6.99	4383.20	<0.05	I	2.0	7.0	2.0	<b>42.0</b>	2.7
	9/16/2002		7.95	4382.24	<0.05	I	2.0	<b>6.</b> 20	2.0	<b>2</b> .0	1.7
	12/30/2002	)	9.37	4380.82	<0.05	ı	<1.0	<1.0	<1.0	<1.0	34.4
	3/13/2003		9.83	4380,34	0.47	i	15.2	<u>6</u>	<u>6</u>	5.9	86
	4/22/2003		9.18	4381.01	Z	1	¥ Z	Σ	M	NM	WZ.
	5/28/2003		8.08	4381.21	Σ	ı	X Z	¥	ΣZ	MN	ΣΝ
	6/20/2003		9.00	4381.19	<0.5	***	0. V	V 7:0	0.I. V	<1.0	20
•	7/31/2003		9.14	4381.05	¥Ν	I	MN	MM	MN	MN	NA
	9/30/2003		9.42	4380.77	<0.05	i	<0.5	<0.5	<0.5	<0.5	1.1
	11/5/2003		9.77	4380,42	ΣN	I	¥	MN	¥N	MN	M
	12/18/2003		68.6	4380.30	0.49	i	10.6	<b>√1</b> ′0	2.1	8.1	868
	3/22/2004		89.6	4380.51	0.31	i	6.2	<1.0	٥. 0.	<1.0	43.5
	6/3/2004		9.75	4380,44	0.038	i	1.0	<1.0	6.0	<1.0	35.8
	9/30/2004		96.6	4380.23	0.366	1	3.5	3.6	13.6	<1.0	127

Page 5 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

	_		_																											*								
	MTRE	(Van)	(: 0)	38.1	99	}		7	0.17	ł	; ا	3.1	i	4.7	}	ı	1.2	1		<1.0	<1.0	5.7	17	1.7	1.9	47.0	3 028	4 230	7,280	3,972	2,535	3,444.0	946	1,454	2,290.0	3,848.0	2,050	1,771
	E-Benzene	(l/gn)		V 1.0	0.1	: <u> </u>	i	7	2:1/	:	! 7	0.17		0	}	ł	<1.0	13.2	i	<1.0	<1.0	√ 7.0 7.0	0.1∠	<1.0	<1.0	0.1⊳	CZ.	17	: <u>Q</u>	S S	£	£	<2.0	<2.0	2.0	2.0	6	8
	Xvienes	(l/gn)		0.5	<b>42.0</b>	1	į	0	?		7	?		<1.0		i	<1.0	i	i	<1.0 <1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	Q2	25	R	2	S	Ð	2.0	<b>6.</b> 20	<b>7</b> 70	0.0	Ç,	20.0
	Toluene	(I/gu)		۸ <u>۲</u> ۰0	<1.0	I	I	Q. [>			7	2.1	ı	<1.0	1	i	<1.0	ł	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	4.0	R	21	S	2	Ð	2	0.0	2.0	2.0	2.0	0	0.
	Benzene	(l/gn)		3.6	<1.0	i	I	<1.0		l	V V	;	ł	<1.0	I	I	<1.0	1	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	7.0	£	Ð	Q Q	£	£	£	2.0	7.0	۵. 0	<b>€</b> 2.0	0 0 1	0
æ	TPH-E	(mg/l)		I	i	i	į	i	i	I	ı		ļ	i	i	I	i	i	i	I	I	l	i	I	I	1		I	Q Q	!	1	ł	I	I	I	į	7	;
Sparks, Nevada	TPHg	(mg/l)		0.43	<0.020	į	i	<0.50	i	i	<0.50	}	i	<0.50	ı	i	<0.50	I	I	I	I	ı	<0.50	I	<0.50	<0.50	3.1	4.4	i	4.0	2.5	3.5	0.95	1.5	2.29	3.85	\$0.05 *	7;x
Spar	Water Level	(ft)		4380.46	4381.03	4380.84	4382.94	4383.38	4382.85	4382.41	4382.08	4381.64	4380.75	4380.89	4383.88	4383.64	4382.85	4383.82	4384.53	4384.24	4382.25	4380.51	4379.88	4380.60	4381.17	4387.94	91.29	91.07	89.27	86.68	89.85	89.67	79.30	89.94	89.30	96'68	AN S	4361.47
	DTW	(¥)		9.73	9.16	9.35	7.25	6.81	7.34	7.78	8.11	8.55	9.44	9.30	6.31	6.55	7.34	6.37	2.66	5.95	7.94	89.6	10.31	9.59	9.02	2.25	8.73	8.95	10.75	10.04	10.17	10.35	^20.72	10.08	10.72	10.06	NA C	۸ ک ک
	MPE	€																									100.02										240046	4370180
		Date		12/29/2004	3/23/2005	4/14/2005	5/27/2005	6/29/2005	7/25/2005	8/30/2005	9/29/2005	10/31/2005	11/30/2005	12/29/2005	1/24/2006	2/1/2006	3/1/2006	4/27/2006	5/31/2006	6/23/2006	9/8/2006	12/28/2006	3/26/2007	6/1/2007	9/7/2007	1/4/2008	4/29/1999	8/3/1999	2/15/2000	6/5/2000	9/5/2000	11/14/2000	2/20/2001	6/13/2001	31/12/2001	11/16/2001	2/0/2004	0/ 0/ A00
	Well	Number	,	M W 4	Cont.																						MW-5											

Page 8 of 28

Page 7 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Snarks, Nevada

	ì	1																																
	MTBE	(ug/l)	SZ*	1.378	1.522	N N	Z	1,100	Z	44	N	292	782	628	792	530	431	i	I	280	1	1	220	I	I	120	i	I	200	1	I		130	130 76
	E-Benzene	(l/gn)	sn.	<1.0	<2.0	NM	ZZ	<1.5	ZZ	<0.5	MN	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	i	ł	<1.0	i	i	<1.0	ı	į	<1.0	ı	I	<1.0	1	I		√ 7.0	0.1∨ 1.0
	Xylenes	(ng/l)	sN.	<1.0	2.0	M	M	<1.5	ΣN	<0.5	Ν̈́Ν	<b>4</b> 2.0	<b>2</b> .0	2.0	2.0	<b>2.0</b>	2.0	i	j	<1.0	ì	i	<1.0	į	ł	<1.0	į	ı	0.1×	1	1	*	0. V	0. 2. ∆ 3. 0.
	Toluene	(l/gn)	*NS	<1.0	2.0	MM	MM	<1.5	NM	<0.5	MM	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	i	I	<1.0	ı	i	<1.0	I	I	<1.0	į	i	<1.0	1	. ]	,	0.1	0.0 V V
	Benzene	(l/gn)	sN*	<1.0	<b>6.7</b>	MN	MN	<1.5	MN	<0.5	MZ	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	I	I	<1.0	ì	Ī	<1.0	i	I	<1.0	i	i	<b>61</b> ,0	1	1	7	?	0.T 7
æ	TPH-E	(mg/l)	1	ı	Ì	i	I	I	i	I	I	I	I	I	I	i	I	I	i	i	ı	i	i	i	i	1	I	I	4	1	i		İ	
Sparks, Nevada	TPHg	(mg/l)	sn.	1.38	1.52	MZ	Σ	0.67	MN	0.64	ΣΝ	0.77	0.78	0.63	0.792	0.530	0.431	I	i	<0.50	I	i	<0.50	I	i	<0.50	į	i	<0.50	1	***			
Spar	Water Level	( <del>t)</del>	4380.66	4379.94	4379.77	4380.04	4380.17	4380.32	4379.97	4379.79	4379.59	4379.49	4379.65	4379.55	4379.54	4379.13	4380.30	4380.21	4381.33	4381.42	4381.13	4380.77	4380.71	4380.34	4379.90	4380.23	4382.49	4382.37	4381,94	4382.14	4382,87	4382 54	- 0.400	4381.18
	DTW	<b>(#</b> )	9.70	10.42	10.59	10.32	10.19	10.04	10.39	10.57	10.77	10.87	10.71	10.81	10.82	11.23	10.06	10.15	9.03	8.94	9.23	9.59	9.65	10.02	10.46	10.13	7.87	7.99	8.42	8:22	7.49	7 83	100	9.18
	MPE	<b>æ</b>																																
		Date	9/16/2002	12/30/2002	3/13/2003	4/22/2003	5/28/2003	6/20/2003	7/31/2003	9/30/2003	11/5/2003	12/18/2003	3/22/2004	6/3/2004	9/30/2004	12/29/2004	3/23/2005	4/14/2005	5/27/2005	6/29/2005	7/25/2005	8/30/2005	9/29/2005	10/31/2005	11/30/2005	12/29/2005	1/24/2006	2/1/2006	3/1/2006	4/27/2006	\$/31/2006	6/23/2006		9/8/2006
	Well	Number	MW-5	Cont.																														

Page 8 of 28

MTBE (ng/l) 6.7 0.7 2.0 2.0 2.0 37 6.0 61 Z 0.5 1.7 X 0.1> X Z 0... E-Benzene (l/gn) <1.0 <u>^1.0</u> 2.0 6.0 0.7 2.0 2.0 0.1∨ 0.2  $\frac{\mathbf{X}}{\mathbf{Z}}$ 4.0 × X 0.5 M <1.0 1.0 <1.0 <1.0 0.1> Toluene Xylenes (l/gn) <1.0 <1.0 7.0 2.0 2.0 6.0 2.0 2 2.0 2.0 200 <u>^1.0</u> 2.0 <u>∧</u>  $\mathbb{Z}$ × Σ 0.5 2.0 6.0 M 2.0 △1.0 6.0 (l/gn) 1.01.01.01.0 6.0 2.0 2.0 2.0 2.0 2.0 1.0 8  $\frac{\mathbb{Z}}{\mathbb{Z}}$ ¥ ∆ 1.0 ¥ 0.5 M 1.0 0.1∨ 1.0 0.1> <u>^1.0</u> △1.0 1.0 Benzene (l/gn) <1.0 1.01.0 0.7 0.7 20.0 6.0 2.0 2.0 <u>^</u> ∆ 1.0 0.5 X ¥ Z Σ 1.0 <1.0 <u>^.</u>i.0 0.1∨ 1.0 WCSD-Getto Transportation Facility, TPH-E (mg/l) 1 1 Sparks, Nevada TPHg (mg/l) <0.50 <0.05 <0.05 <0.05 <0.5 **0.5** <0.5 <0.05 <0.05 <0.05 <0.02 <0.02 **0.5** ¥ M X Σ <0.02 <0.01 <0.01 <0.02 Water Level 4379.90 4379.85 4379.49 4380.18 4379.97 4379.67 4379.66 4379.74 4379.98 4379.70 4380.05 4379.78 4379.42 89.82 89.68 89.58 79.33 89.50 89,44 4379.57 1379.41 4379.87 4379.41 4380.25 # 89.61 4380.76 4379.70 4380.50 1380.07 ¥ covered by car DTW 10.51 ^19.94 10.09 9.45 9.59 9.69 9.66 9.77 9.83 9.30 Œ 9.82 9.74 9.43 9.50 9.70 9.99 10.07 9.91 9.78 10.07 10.06 9.81 9.61 9.23 9.41 \*4389.48 MPE 99.27 **E** 1/14/2000 2/15/2000 6/5/2000 1/16/2001 9/16/2002 2/30/2002 1/4/2008 9/5/2000 2/20/2001 6/1/2007 9/7/2007 8/3/1999 6/13/2001 8/28/2001 3/13/2003 4/22/2003 2/18/2003 6/6/2002 5/28/2003 3/6/2002 6/20/2003 7/31/2003 9/30/2003 11/5/2003 3/22/2004 12/29/2004 Date 9/30/2004 3/23/2005 6/3/2004 4/14/2005 5/27/2005 6/29/2005 7/25/2005 8/30/2005 9/29/2005 Number 9-MM MW-5 Well Cont.

Summary of Ground-Water Monitoring Data

TABLE 1

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

Well		MPE	DTW	Spa Water Level	Sparks, Nevada	a TPH-E	Benzene	Toluene	Xvienes	R-Renzene	Мтвр
	Date	<b>(#</b> )	€	(#)	(mg/l)	(mg/l)	(l/gn)	(l/gn)	(l/gn)	(l/gu)	(l/g/l)
			;								
	10/31/2005		09.6	4379.88	I	I	I	1	i	i	i
	11/30/2005		9.78	4379.70	I	i	i	I	I	ı	•
	12/29/2005		9.32	4380.16	<0.50	i	<1.0	<1.0	<1.0	V 10	- F
	1/24/2006		7.42	4382.06	i	i	i	I			? !
	2/1/2006		7.47	4382.01	I	i	ł	I	i	i	
	3/1/2006		7.72	4381.76	<0.50	ļ	<1.0	<1.0	V V	7	1 7
	4/27/2006		8.10	4381.38	i	i		}	7 1		0.17
	5/31/2006		7.16	4382.32	ł	I	ł			•	İ
	6/23/2006		7.74	4381.74	i	1	7	7	1 7	1 7	1 ;
	9/8/2006		8.73	4380 75			7 7	? ?	7 7	V.1.0	0.15
	12/28/2006		9 78	4370 70			? ?	? ?	2 7	V.1.0	0.1>
-	3/26/2007		10.48	4370.00		l	2.5	0.7	0.12	0.1>	<1.0
	2/1/2007	¥	10.40	4579.00	<0.50	i	0.1>	0.I^	<1.0 <1.0	<1.0	<1.0
	0/1/200/		10.15	4379.33	i	i	<1.0	√ 7.0	<1.0	<1.0	<1.0
	2/1/2001		10.04	4379.44	<0.50	i	<1.0	<1.0	<1.0	<1.0	<1.0
	1/4/2008		9.16	4380.32	<0.50	ł	47.0	<1.0	<1.0	<1.0	√1.0
	8/3/1999	99.40	8.65	90.75	Ð	l	2	50	48	35	2
	2/15/2000		10.14	89.26	i	Ð	2	2	2	SE	2 5
	6/5/2000		9.64	89.76	2	i	2	2	2	2	9 5
	9/5/2000		8.6	89.60	R	R	2	2	2	2 5	<u> </u>
	11/14/2000		9.93	89.47	2	ı	£	2	2	2	2 5
	2/20/2001		^20.16	79.24	<0.5	I	2.0	2.0	2.0	000	50
	6/13/2001		98.6	89.54	<0.5	I	2.0	2.0	2.0	2.0	4.4 4.4
	8/28/2001		9.6	89.44	<0.5	I	2.0	<b>2.0</b>	<b>2</b> .0	<2.0	36.9
	11/16/2001		10.01	89.39	0.17	ı	77.0	<b>0.</b> 7	2.0	<2.0	168.3
	3/6/2002	;	Y.	NA	<0.05	i	75.0	<b>2</b> .0	<b>2.0</b>	<2.0	204
	6/6/2002	4389.63	9.10	4380.53	0.28	i	<b>7</b> 70	2.0	2.0	<2.0	284
	9/16/2002		9.75	4379.88	0.46	I	2.0	<b>2</b> .0	2.0	2.0	457
	12/30/2002		9.98	4379.65	0.36	I	<1.0	<1.0	<1.0 <1.0	<1.0	363
	3/13/2013	ä	10.04	4379.59	0.48	ł	2.0	2.0	0.7	2.0	476
	4/22/2003		9.93	4379.70	M	I	ΣX	ΣN	MM	MN	ΣZ
	\$/28/2003		9.66	4379.97	¥	I	MZ	MZ	MM	ΣX	ΣZ
	6/20/2003		29.6	4379.96	<0.5	I	<1.0	<1.0	<1.0	<1.0	390
	7/31/2003		9.92	4379.71	N.	I	Σ	MN	MN	ZZ	N Z
	9/30/2003		10.10	4379.53	0.18	i	<0.5	<0.5	<0.5	0.8	176
	11/5/2003		10.23	4379,40	Σ̈́Z	I	WN	Σ	MN	MN	¥

Page 9 of 17

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

Well		LE S		Spa	Sparks, Nevada	æ					
Mumbo-	į	HAIN.	DIW	Water Level	TPHg	TPH-E	Benzene	Toluene	Xvlenee	R-Renzene	7777
Maniber	Date	€	€	( <del>ll</del> )	(mg/l)	(mg/l)	(l/gn)	(l/an)	(l/an)	(ha/l)	MIBE
2 110									(1.6.	(IÆn)	(ng/1)
MW-/	12/18/2003		10.28	4379.35	0.033	į	7	7	9	3	
Cont.	3/22/2004		96.6	4379.67	0.13		? ;	? ;	0.2	<1.0	33.5
	6/3/2004		10 14	4370 40	515	i	0.1/	0.1^	<b>4</b> 7.0	<1.0	131
	9/30/2004		10.40	CF.C.C.	0.150	i	v. V.	0.    -	۵. 0	<1.0	196
	12/20/2004		10.40	43/9.23	0.147	I	<1.0 <	0. <u>I</u> >	<1.0	0	147
	2/12/12/04		10.54	4379.09	0.150	ı	<1.0	<1.0	0.0	2 7	140
	3/23/2003		9.49	4380.14	0.157	į	<1.0 <1.0	· ∇	0	? 7	149
	4/14/2005		9.63	4380.00	1	I		2.7	75.0	. 0.1.>	157
	\$/27/2005		8.86	4380.77	į		I	I	I	I	1
	6/29/2005		90.6	4380 57	000	l	1 ;	1	ı	i	i
	7/25/2005		927	4380.26	00.0	I	0.I.>	<b>0.</b> [∨	<1.0	<1.0	58
	8/30/2005		0 61	4280.00	l	I	I	i	I	I	ı
	0/26/2006		2.01	4380.02	I	1	ı	i	i	i	į
	10/21/2005		10.68	4378.95	<0.50	ł	<1.0	<1.0	<1.0	<b>~</b>	1 3
	10/31/2005		10.11	4379.52	I	į	ı		2	2.7	8
	11/30/2005		10.06	4379.57	ļ	ı		l	l	l	1
	12/29/2005		9.52	4380.11	050>		1 ;	I	I	1	I
	1/24/2006		7.61	4382.02	0.0	į	0.1	0.1.	√ 7.0	<1.0	140
	2/1/2006		7 60	4301.02	•	l	ı	1	i	ļ	ŀ
	3/1/2006		0.7	4361.94	1	I	ı	ł	i	ł	
	4/27/2006		¥. 6	4381.69	<0.50	I	<1.0	<1.0	<1.0	<1.0	380
	2007/17/3		0.02	4381.61	I	I	ł	į	ı	:	8
	0/3/1/2000		7.58	4382.05	I	ł	I	į		I	ŀ
	9/23/2006		8.04	4381.59	ļ	į	7	7	1 ;	1	I
	9/8/2006		9.10	4380.53	ł	İ	? ?	0.17	0.T.	<1.0	190
	12/28/2006		10.02	4370 61	l	i	0.1.	VI.0	<1.0	<1.0	150
	3/26/2007		10.78	1270 05	1	Ì	0.1>	V.    -	<b>0.</b> I≻	<1.0	210
	6/1/2007		10.40	4370.73	00.00	I	0.1 <1.0	√1.0	<1.0	<1.0	190
	9/7/2007		10 32	4370.23	1	ı	0.I ✓	<1.0 <1.0	<1.0	<1.0	70
	1/4/2008		10.01	10.6164	<0.50 -	ŀ	<1.0	√1.0 	<1.0	<1.0	140
			11.21	4377.52	<0.50	ı	0.₽	4.0	0.1⊳	7.0	4.0
MW-8	4/26/2002		9.87	ΔN	20 00					a)	
	6/6/2002	4389.09	8.71	1280.20	6.07	i	0.25	2.0	2.0	2.5	2.0
•	0/16/2002	20120		4300.30	<0.0>	i	0.2	2.0	2.0	00	7
	10/20/07/07		9.43	4379.66	<0.05	ı	0.2	2.0	0.0	e ç	0.37
	2002/05/21		9.35	4379.74	<0.05	i	<1.0	0.12		? ?	0.0
	3/13/2003		9.53	4379.56	<0.05	I	000	֓֞֝֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֡֓֓֓֓֓֡֓֓֓֡	? ?	0.7	1.4
	4/22/2003		9.38	4379.71	Z	į		2.5.0	ָ ֓֞֞֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֡֓֓֡֓֓֓֡֓֡֓֓֓֡֓֡֓֡֓֡֓	0.75	2.0
	5/28/2003		9.14	4379.95	2	1	MIN.		Z ;	N.	Σχ
	6/20/2003		9.24	4379.85	× 0×	ļ	MIN T	WN :	W.	ZZ Z	NN NN
					2.0	I	۲.0 دا.0	-	1.4	<1.0	6.1
	J.										<u> </u>

age 10 of 2

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

AFFDE	(//o/l)		Z :		17 P	0.7.7 V	11.7	17.3	2.4		}	ļ			ņ	7.3	3	1	2.3	-    -	i Na	1.6	1	I	1.5	5.8	<1.0	<1.0	44	33	3	103.3	70,	780	647	793
P Denzone	(ug/l)		NA C		V 10	0.5	. 0.1>	V 10	0.15	V 1.0	1	I	I	i	ı	<1.0	•	i	<1.0	1	ļ	<1.0	i	i	<1.0	<1.0	<1.0	<b>0.1</b> ≻	<1.0	<u>  \</u>	}	2.0	Ç	30	√1,0 √1,0	6.5
Tolmene Xvlenes			7 Y		0	20.0	200	0.15	2.0	20	1	I	į	ļ	i	0.1>	i	i	<1.0	-	i	<1.0	į	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		200	0.0	<b>3</b> 6	<1.0	<b>2</b> .0
Tolnene	(ug/l)	1	7 (V	<u> </u>	0.10	<1.0	<1.0	<1.0	<1.0	<1.0	I	I	I	ŀ	I	<1.0	i	ı	<1.0	I	l	<1.0	I	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		3.1	2,0	2.0	<1.0	0.0
Renzene	(ug/l)	Ž	\$ 0>	Z Z	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	ļ	I	1	ı	i	<1.0	i	ı	<1.0	l	ı	<1.0	ı	1	<1.0	<1.0	<1.0	<1.0	<1.0	4.0		22.0	0,2	6,3	<b>₹</b>	200
TPH-F		1	I	i	I	i	į	i	!	ļ	I	I	I	į	i	I	i	i	i	ı	i		l	į	I	ŀ	I	I	i	I		11-18	•	į	1	1
TPHe	(mg/l)	Ę	<0.05 0.05	XX	0.013	<0.020	<0.020	0.017	<0.01	<0.02	i	i	I	I	I	<0.50	•	i	<0.50	I	I	<0.50	I	I	I	i	I	<0.50	ı	<0.50		<0.05	0.23	0.79	0.63	62.0
Water Level	(#)	4379.58	4379.57	4379.41	4379.37	4379.80	4379.89	4379.28	4379.37	4380.15	4380.04	4380.73	Curb	i	ŀ	I	1	1	ı	1	i	i	i	Car	i	i	I	1	I	i	ocate	NA	4383.11	4379,54	4379.52	4379,44
DTW	( <del>U</del> )	9.51	9.52	89.6	9.72	9.29	9.20	9.81	9.72	8.94	9.05	8.36	Covered by	7.97	8.28	8.34	8.47	8.54	8.17	90.9	6.14	6.46	6.54	Covered by Car	6.72	7.81	8.61	9.45	8.93	8.95	Unable to locate	12.25	9.11	12.68	12.70	12.78
MPE	( <del>U</del> )																																4392.22			
	Date	7/31/2003	9/30/2003	11/5/2003	12/18/2003	3/22/2004	6/3/2004	9/30/2004	12/29/2004	3/23/2005	4/14/2005	5/27/2005	**6/29/2005	7/25/2005	8/30/2005	9/26/2005	10/31/2005	11/30/2005	12/29/2005	1/24/2006	2/1/2006	3/1/2006	4/27/2006	5/31/2006	902/23/9	9/8/2006	12/28/2006	3/26/2007	6/1/2007	9/7/2007	1/4/2008	4/26/2002	6/6/2002	9/16/2002	12/30/2003	3/13/2003
Well	Number	MW-8	Cont.																													6-WW		-		

Page 11 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

Well		MPF	DTW	Water I evel	TPHa	T-Har	Renzene	Tolinene Vulenee	Vydonog	P. Denzene	AATOD
Number	Date	€	€	<b>(±)</b>	(mo/l)	(mo/l)	(//۵11)	(l'ad)	Charles	(na/l)	(hed)
		/	7417	<b>XX</b>	(1)	6	( Ann.	7.6-1	/*/A"\	(1/Bm)	(1/Am)
MW-9	4/22/2003		12.63	4379.59	MN	i	MX	Σχ	MN	NM	MN
Cont.	5/28/2003		12.31	4379.91	ΣN	ı	MN	MN	MN	MM	MM
	6/20/2003		12.54	4379.68	0.51	ı	<1.5	<1.5	<1.5	<1.5	840
	7/31/2003		12.75	4379.47	MN	i	M	MN	MN	MN	MX
	9/30/2003		12.72	4379.50	0.93	I	<0.5	<0.5	<0.5	<0.5	927
	11/5/2003		12.89	4379.33	MN	i	MN	MN	M	MN	MN
	12/18/2003		12.96	4379.26	1.15	i	<1.0	<1.0	2.0	<1.0	1,148
	3/22/2004		12.57	4379.65	1.13	1	<1.0	<1.0	2.0	<1.0	1,129
	6/3/2004		12.45	4379.77	0.82	l	<b>0.1</b>	<1.0	<b>6</b> 2.0	<1.0	820
	9/30/2004		13.03	4379.19	1.42	ł	<1.0	<1.0	<1.0	<1.0	1,420
	12/29/2004		13.02	4379.20	0.91	I	<1.0	<1.0	<b>2.0</b>	<1.0	912
	3/23/2005		12.26	4379.96	0.581	I	<1.0	0.1>	2.0	<1.0	581
	4/14/2005		12.29	4379,93		I	i	I	i	i	
	5/27/2005		12.02	4380.20	I	I	i	i	i	1	i
	6/29/2005		11.88	4380.34	<0.50	i	<1.0	<1.0	<1.0	<1.0	290
	7/25/2005		12.15	4380.07	1	i	1	I	ł	i	- <u>1</u>
	8/30/2005		12.50	4379.72	i	I	i	1	i	i	
	9/26/2005		12.55	4379.67	<0.50	i	<1.0	<1.0	<1.0	<1.0	710
	10/31/2005		12.67	4379.55	i	l	i	i	i	i	. 1
	11/30/2005		12.80	4379.42	i	i	i	I	i	I	ł
	12/29/2005		12.08	4380.14	<0.50	I	<1.0	<1.0	<1.0	<1.0	380
ŧ	1/24/2006		10.43	4381.79	ł	I	ıİ	I	i	ł	i
	2/1/2006		10.49	4381.73	1	i	l	i	1	i	I
	3/1/2006		10.68	4381.54	1.2	1	o:1>	<1.0	<b>~1</b> .0	<1.0	1,200
	4/27/2006		10.83	4381.39	1	ı	į	I	I	i	ľ
	5/31/2006		10.49	4381.73	1	1	1	I	1	i	ł
	6/23/2006		11.00	4381.22	i	i	7.0	o.  ∨	<b>~1</b> .0	<1.0	920
	9/8/2006		12.05	4380.17	i	I	7.0	0.1>	<1.0	<1.0	740
	12/28/2006		12.79	4379.43	i	ı	<1.0	<1.0	<1.0	<1.0	800
	3/26/2007		13.58	4378.64	<0.50	i	<1.0	<1.0	<1.0	<1.0	630
	6/1/2007		13.11	4379.11	i	I	<1.0	<1.0	√1.0	<1.0	. 510
	9/7/2007		13.09	4379.13	<0.50	ı	<1.0 <1.0	<b>√1.</b> 0	<1.0	<1.0	390
	1/4/2008		12.47	4379.75	<0.50	l	<1,0	7.0	<1.0	<1.0	320
MW-10	4/26/2002		0.81	NA.	<0.05	1	62.0	00	000	0.00	6
	6/6/2/00	1380 AN	11 00	1277 KD			3 6	? ?	3 6	3 6	9 6
	7007/0/0	4507.50	11,70	40.1104	90.0V	•	). 5.0	27	2	0.7.5	0.75

Page 12 of 28

Page 13 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Snarks, Nevada

	ı		ı															#1 25	:											*								
	MTBE	(l/gu)	<b>3 3</b> 8	0 1	7.6	17.0		1 %	? <u>&gt;</u>	4.2	Z	37	44.1	299	71.1	113	118	I	İ	100	-	: I	170	}	1	190	1	. [	280	I	I	260	. 230	210	210	360	200	120
	E-Benzene	(l/gu)	ç	7	2.0		E Z	0.12	Σ	<0.5	Z	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	ı	ı	<1.0	1	I	<1.0	1	I	<1.0	1	ļ	<1.0	I	i	<1.0	<1.0	<1.0	<1.0	0,12	<b>V</b>	2 ∇
	Xylenes	(l/gu)	0	3 7	2 0	Ž	Z	<1.0	Z	<0.5	MN	<b>4</b> 2.0	2.0	2.0	<1.0	2.0	2.0	i	I	<1.0	I	i	<1.0	I	ı	<1.0	ł	į	<1.0	ı	ı	<1.0	<1.0	<1.0	√1.0	<b>√1</b> ′0	0 7	<1.0
	Toluene	(ug/l)	Ş	Ş 7	0	ž	Z	<1.0	M	<0.5	MN	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	i	I	<1.0	i	I	<1.0	i	i	<1.0	i	1	<b>~1.</b> 0	i	i	<1.0	<1.0	<1.0	<1.0	<b>41.0</b>	0'!V	<1.0
	Benzene	(l/gn)	€ 0.0	0 7	0.0	Z	ΣZ	<1.0	MN	<0.5	MN	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1	i	<1.0	i	i	<1.0	I	I	<1.0	i	2	<1.0	ı	ı	<1.0	<1.0	<1.0	<1.0	0.1≻	0.1>	0' <b> </b> ∀
æ	TPH-E	(mg/l)	ì	ŀ	i	i	I	i	I	ı	I	I	i	ı	i	ı	I	I	i	i	I	i	i	I	i	i	ł	***	I	i	ı	i	ł	i	ł	i	1	1
Sparks, Nevada	TPHg	(mg/l)	<0.05	<0.05	<0.05	MN	MN	<0.5	MN	<0.05	ΜN	0.04	0.044	0.067	0.071	0.11	0.118	I	i	<0.50	i	i	<0.50	I	I	<0.50	i	1	<0.50	I	I	ł	I	1	<0.50	1	<b>0.50</b>	≪0.50
Spar	Water Level	(¥)	4379.88	4379.60	4379.50	4379.64	4379.89	4379.81	4379.62	4379.42	4379.40	4379.31	4379.66	4379.71	4379.24	4379.09	4379.96	4379.93	4380.63	4380.40	4380.16	4379.86	4379.79	4379.60	4379.49	4380.08	4381.81	4381.75	4381.54	4381.46	4381.82	4381.36	4380.26	4379.48	4378.80	4379.14	4379,29	4379.79
	DTW	€	9.62	9.90	10.00	9.86	9.61	69.6	9.88	10.08	10.10	10.19	9.84	9.79	10.26	10.41	9.54	9.57	8.87	9.10	9.34	9.64	9.71	9.90	10.01	9.42	7.69	7.75	7.96	<b>8</b> .04	2.68	8.14	9.24	10.02	10.70	10,36	10,21	9.71
	MPE	€																																				
		Date	9/16/2002	12/30/2002	3/13/2003	4/22/2003	5/28/2003	6/20/2003	7/31/2003	9/30/2003	11/5/2003	12/18/2003	3/22/2004	6/3/2004	9/30/2004	12/29/2004	3/23/2005	4/14/2005	5/27/2005	6/29/2005	7/25/2005	8/30/2005	9/26/2005	10/31/2005	11/30/2005	12/29/2005	1/24/2006	2/1/2006	3/1/2006	4/27/2006	5/31/2006	6/23/2006	9/8/2006	12/28/2006	3/26/2007	6/1/2007	9/7/2007	1/4/2008
	Well	Number	MW-10	Cont.																																		

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks, Nevada

														24																*						
	MTBE	(r/An)	<1.0	<0.5	ZZ	<1.0	<1.0	o.1>	<1.0	<1.0	<1.0	ı	ı	<1.0	l		<1.0		1	<1.0	-	ł	<1.0	ı	ł	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	√1.0	1.3	\$ 0	SN.	41.0
	E-Benzene	(1/Sn)	<1.0	<0.5	MN	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	I	i	<1.0	I	I	<1.0	Ī	ł	<1.0	ì	ı	<1.0	ł	ı	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	⊲1.0	<1.0	\$0.5	SZ	<1.0
	Xylenes	(rgn)	<1.0	<0.5	¥	2.0	<b>5</b> .0	2.0	<1.0	<b>42.0</b>	<b>2</b> .0	l	ı	<1.0	ı	ı	<1.0	I	I	<1.0	ł	I	<1.0	I	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.5	SN.	8
	Toluene	(1/Sm)	<1.0	<0.5	MN	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	I	I	<1.0	I	I	<1.0	I	i	<1.0	i	I	<1.0	i	i	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<b>61.0</b>	<1.0	<0.5	SN.	41.0
	Benzene		<1.0	<0.5	MN	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	i	I	<1.0	I	ł	<1.0	ı	I	<1.0	i	I	<1.0	I	I	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.1</b> ⊳	<1.0	<0.5	SN.	<1.0
	TPH-E			i	ł	I	I	i	i	ł	i	I	i	ı	I	I	I	I	I	I	i	I	I	I	I	ı	ı	i	ı	I	ł	ł	ŀ	1	SZ.	3
Sparks, ivevada	TPHg (me/l)		<1.0	<0.05	MN	<0.02	<0.02	<0.02	<0.01	<0.01	<0.02	ı	ı	<0.50	I	i	<0.50	İ	1	<0.50	ł	i	<0.50	ŀ	1	I	I	ı	<0.50	I	<0.50	<0.50	<1.0	<0.05	*NS	<0.02
JRdc	Water Level		4380.42	4379.63	4379.53	4379.47	4379.90	4379.99	4379.41	4379.48	4380.25	4380.20	4380.85	4380.58	4379.37	4380.05	4379.97	4379.86	4379.71	4380.36	4382.03	4381.85	4381.86	4381.70	4381.89	4381.50	4380.48	4379.66	4378.66	4379.39	4379.52	4379.87	4378.75	4379.56	SN.	4379.38
	<u>}</u> €	5	9.49	10.28	10.38	10.44	10.01	9.92	10.50	10.43	9.66	9.71	90.6	9.33	10.54	98.6	9.94	10.05	10.20	9.55	7.88	8.06	8.05	8.21	8.02	8.41	9.43	10.25	11.25	10.52	10.39	10.04	10.30	9,49	SN.	29.6
	MPE (#)		4389.91	•																													4389.05			
	Date		8/1/2003	9/30/2003	11/5/2003	12/18/2003	3/22/2004	6/3/2004	9/30/2004	12/29/2004	3/23/2005	4/14/2005	5/27/2005	6/29/2005	7/25/2005	8/30/2005	9/26/2005	10/31/2005	11/30/2005	12/29/2005	1/24/2006	2/1/2006	3/1/2006	4/27/2006	5/31/2006	6/23/2006	9/8/2006	12/28/2006	3/26/2007	6/1/2007	9/7/2007	1/4/2008	8/1/2003	9/30/2003	11/5/2003	12/18/2003
117.71	well Number		MW-11																														MW-12			

Page 14 of 28

Summary of Ground-Water Monitoring Data WCSD-Getto Transportation Facility,

	ı		ı																			. 6																			
		MTBE	(mB)1)	1,	7:7	?	0.7	0.7	<b>0.1</b> >	ı	ł	<1.0	I	ł	<1.0	1	i	7	<b>2</b>		1 :	7:1	I	ł	،<1.0	<1.0	<1.0 <1.0	2.6	1.5	SN	SN	e	1,907	6,360	4.328	4.544	1041.0	682	1.415	2067.0	684.0
	2 2	E-Benzene	/; A_\	012	2	? 7	? 7	9.5	0.17	I	ı	<1.0	I	1	<1.0	i	i	0 7	1		1 7	0.17	1	i	<1.0	<1.0	<1.0	<1.0	<1.0	NS	SN		£	£	Q	Ð	Q.	<2.0	<2.0	0.5	0.5
	V	(ue/l)	*	0.0	0	ç	; ;	? ?	2.7	i	I	<1.0	I	i	<1.0	ı	i	<1.0	ı	į	710	, ,	ı	I	0. <u>I</u> >	√1.0 √1.0	<1.0	o:1>	<1.0	SN	NS		Q	£	R	Ð	£	2.0	<b>2</b> .0	2.0	2.0
	Tolyana	(ug/l)		<1.0	0.	0.1	V 7	0.1	?: <del>.</del>	ł	I	<1.0 <1.0		I	0.1>	i	I	0.1>	ı	ı	0.10		Ì	1	0.1>	<b>0.1</b> >	0.T ∨1.0	<b>~1</b> .0	<1.0	SN	NS	!	2	2	£	2	Q	<b>6</b> .2	2.0	۵. ٥	Š
	Renzene	(l/gu)		<1.0 <1.0	<1.0	<1.0	0.	V 10		I	1	√ 7.0		i	V-1.0	I	I	<1.0	ı	ı	<1.0	1		1 ;	0.12	0.12	o:[>	<1.0 <1.0	<1.0	NS	SN	E		2	2	2	Ð	<b>2</b> .0	7.0	3.4	<b>42</b> :0
g	TPH-R	(mg/l)		ł	I	ł	I	į	ı		i	١.	eriai	ı	I	I	i	I	I	ł	i	Ì	į	!	I	ł	i	ł	i	ı	ł		! !	2	1	ł	ı	ı	i	į	77
Sparks, Nevada	TPHe	(mg/l)		<0.02	<0.02	<0.01	<0.01	<0.05	ł			<0.50 5	Base Mat	1	<0.50	i	I	<0.50	I	I	<0.50	1	1		1	i	1	<0.50	1 }	SZ	S.	10	7:1	1 3	4. ' ئ	4.55	1:1	0.69	1.42	2.07	0,69
Spai	Water Level	(ft)		4379.85	4379.90	4379.32	4379.38	4380.14	4380.08	4380.73	4200.70	4380.48	o 14	1 6	43/9.85	4379.72	4379.62	4380.31	4382.28	4382.22	4381.75	Covered by Car	4381.84	438136	4380 32	4370.54	4379.34	43/8.39	45/9.30	l	1	91.21	01.00	90.08	69.60	69.79	89.58	79.32	89.84	90.03 80.03	67,84
	DTW	(#)		9.20	9.15	9.73	29.6	8.91	8.97	8.32	6 57	Well Not I	0.15	2.15	9.40	6,55	9.43	8.74	6.77	6.83	7.30	Cove	7.21	7.69	8.73	0 51	10.46	0.40	27.7		MINI	8.73	10.75	10.00	10.07	10.15	10.30	20.02	10.10	10.10	10.10
	MPE	€																														99.94									
		Date	7/11/1004	5/22/2004	6/3/2004	9/30/2004	12/29/2004	3/23/2005	4/14/2005	5/27/2005	6/29/2005	7/25/2005	8/30/2005	\$002/96/6	10/31/2005	11/30/2005	11/30/2003	1/24/2005	27,17000	2/1/2006	3/1/2006	4/27/2006	5/31/2006	6/23/2006	9/8/2006	12/28/2006	3/26/2007	6/1/2007	7000/2/6	1/4/2008		8/13/1999	2/15/2000	6/5/2000	0/2/2000	11/14/2000	2/20/2001	6/13/2001	8/28/2001	11/16/2001	100000
	Well	Number	MW.12	71-W W	Conf.																											RW-1									

Pege 16 of 28

Page 16 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,
Sparks. Nevada

1		MPF	DTW	Spa Water I evel	Sparks, Ivevada	TDIT D	Dengano	T				
2		TARE TO	* 3	water Level	IFHE	ונים	Benzene	Loluene	Xylenes	E-Benzene	MTBE	
Date		Œ	<b>E</b>	€	(mg/l)	(mg/l)	(l/gn)	(ng/l)	(l/gn)	(l/gu)	(l/gn)	
3/6/2002	2		NA	NA	<0.05	ł	2.0	2.0	2.0	0.0	403	
6/6/2002	2	4390.18	8.60	4381.58	1.20	I	2.0	2.0	200	2 <del>.</del> 0	1 200	
9/16/2002	05		10.00	4380.18	0.42	i	0.2	2.0	2.0	2.0	415	
12/30/2002	005		10.38	4379.80	0.26	I	<1.0	<1.0	<1.0	<1.0	259	
3/13/2003	93		10.54	4379.64	0.30	I	<2.0	2.0	2.0	25.0	304	
4/22/2003	93		10.40	4379.78	Σ̈́	ł	MN	MN	MN	ZZ	Z Z	
5/28/2003	003		10.91	4379.27	MN	I	MN	MN	M	Z	Z	
6/20/2003	003		10.62	4379.56	<0.5	i	<1.0	<1.0	<1.0	<1.0	140	
7/31/2003	003		10.51	4379.67	MZ	I	MN	N	MN	ZZ	Z	
9/30/2003	003		10.54	4379.64	<0.05	ı	<0.5	<0.5	<0.5	<0.5	93.5	
11/5/2003	2003		10.85	4379.33	MN	I	MZ	MN	MN	WZ		
718	12/18/2003		10.80	4379.38	0.32	I	<1.0 <1.0	<1.0	2.0	<1.0	318	
77	3/22/2004		10.43	4379.75	0.24	ı	<1.0	<1.0	2.0	Q	240	
6/3/2004	904		10.27	4379.91	<0.02	I	<1.0	<1.0	2.0	<1.0	44.3	
30	9/30/2004		10.84	4379.34	0.102	i	<1.0	<1.0	<1.0	<1.0	102	
/29	12/29/2004		10.78	4379.40	0.150	I	<1.0	<1.0	2.0	<1.0 <1.0	155	
23	3/23/2005		66.6	4380.19	0.132	i	<1.0	<1.0	<b>2</b> .0	<1.0	132	
/14/	4/14/2005		10.06	4380.12	ł	1	i	ł	I	1	1	
77	5/27/2005		9.25	4380,93	i	ı	ł	ł	ı	ł		
736	6/29/2005		9.56	4380.62	<0.50	I	1.8	<1.0	<1.0	<1.0	. 6	
25/	7/25/2005		6.77	4380.41	I		ı	ı	ł	1	: 1	
9	8/30/2005		10.15	4380.03	I	i	i	i	ł	i	ı	
726	9/26/2005		10.23	4379.95	<0.50	i	<1.0	<1.0	<1.0	<1.0	54	
31	10/31/2005		10.34	4379.84	I	ł	I	I	į	i	: 1	
8	11/30/2005		10.51	4379.67	ł	i	i	i	i	i	ļ	
/29	12/29/2005		9.85	4380.33	<0.50	i	<1.0	<1.0	<1.0	<1.0	11	
24/	1/24/2006		7.98	4382.20	-	I	I	i	į	ı		
112	2/1/2006		8.29	4381.89	i	ł	i	i	į	ı	į	
172	3/1/2006		8.31	4381.87	<0.50	ł	<1.0	<1.0	<1.0	<1.0	37	
27/	4/27/2006		8.37	4381.81	I	ł	i	1	1	1	5	
31%	5/31/2006		8.05	4382.13	i	ł	ı	ı	i	ł	ł <b>l</b>	
23/	6/23/2006		8.43	4381.75	I	ı	<1.0	<1.0	<1.0	<1.0	. 23	
9/8/2006	900		9.50	4380.68	l	I	0.1>	<1.0	√ 7.0	0.1≥	5.2	
78	12/28/2006		10.48	4379.70	į	I	<1.0	<1.0 <1.0	<1.0	<1.0	=	
3/26/2007	200		11.42	4378.76	<0.50	i	<1.0	<1.0	<1.0	<1.0	. 64	

Page 17 of 28

TABLE 1
Summary of Ground-Water Monitoring Data
WCSD-Getto Transportation Facility,

	Ĺ.	ı
	MTBE (ug/l)	9 F 7 4
	E-Benzene (ug/l)	<1.0 <1.0 <b>△1.0</b>
	Xylenes (ug/l)	
	Toluene (ug/l)	<1.0 <1.0 <1.0 <1.0 <1.0
	Benzene (ug/l)	<pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre></pre> <pre>&lt;</pre>
æ	TPH-E (mg/l)	111
Sparks, Nevada	TPHg (mg/l)	<0.50 <0.50
Spar	Water Level (ft)	4379.36 4379.41 <b>4380.65</b>
	DTW (ft)	10.82 10.77 9.53
	MPE (ft)	
	Date	6/1/2007 9/7/2007 1/4/2008
	Well	RW-1 Cont.

MPE = Measuring Point Elevation

TPHg = Total Petroleum Hydrocarbons - gasoline

TPH-E = Total Petroleum Hydrocarbons - Extractable

--- = Not Analyzed

ND = Below Laboratory Detection Limits

\*NS/\*NM=Not Sampled, Not Monitored, vehicle parked over the well

\*4389.48=Estimation based on Surveyor's measurement from top of well cap

\*\*MW-8 well head modified after being buried by curb

^ Depth to water considered anomalous on this date; value appears to be 10 feet greater than actual depth.